

FILE NOTATIONS

Entered in MID File

Location Map Pinned

Card Indexed

COMPLETION DATA:

Date Well Completed 6-4-79

W..... WW..... TA.....

51 GW..... OS..... PA.....

Checked by Chief

Approval Letter

Disapproval Letter

Location Inspected

Bond released

State or Fee Land

LOGS FILED

Driller's Log.....

Electric Logs (No.)

E..... I..... Dual I Lat..... GR-N.....

BHC Sonic GR..... Lat..... MI-L.....

CCLog..... CCLog..... Others.....

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

BLM-SURFACE

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☒OTHER ☐SINGLE
ZONED ☒MULTIPLE
ZONED ☐

2. NAME OF OPERATOR

CIG EXPLORATION, INC.

3. ADDRESS OF OPERATOR

P. O. BOX 749, DENVER, CO 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

At surface

1823' FNL & 2090' FEL, Section 13, T10S, R20E

At proposed prod. zone

SAME AS ABOVE

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

APPROXIMATELY 15 MILES SOUTHEAST OF OURAY, UTAH

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST

PROPERTY OR LEASE LINE, FT.

(Also to nearest driz. unit line, if any)

550'

16. NO. OF ACRES IN LEASE

2002.77

17. NO. OF ACRES ASSIGNED

TO THIS WELL
N/A

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED, APPROXIMATELY

3000'

19. PROPOSED DEPTH

6800'

20. ROTARY OR CABLE TOOLS

ROTARY

21. ELEVATIONS (Show whether DP, RT, CR, etc.)

5098'

UNGRADED GROUND

22. APPROX. DATE WORK WILL START*

NOVEMBER 15, 1978

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	9-5/8"	36#	200'	125 sx
7-7/8"	4-1/2"	11.6#	6800'	CIRCULATE CEMENT BACK TO SURFACE

FRESH WATER AQUIFERS WILL BE PROTECTED WHEN THE LONG STRING IS RUN AND CEMENT IS
CIRCULATED TO SURFACE.

SEE ATTACHED SUPPLEMENTS FOR FURTHER INFORMATION:

- (1) 10-POINT PROGRAM
- (2) BOP SCHEMATIC
- (3) 13-POINT PROGRAM
- (4) PLAT

State of Utah, Dept. of

Division of

1500

Salt Lake City, Utah

GAS WELL PRODUCTION HOOKUP TO FOLLOW ON SUNDRY NOTICE.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

F. R. MIDDLEE

TITLE DISTRICT SUPERINTENDENT

DATE September 22, 1978

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

A. P. K. Zola

TITLE

DISTRICT ENGINEER

DATE DEC 11, 1978

CONDITIONS OF APPROVAL, IF ANY:

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL
TO OPERATOR'S COPYNECESSARY FLARE OFF GAS BURNING DURING AND
COMPLETION APPROX. 10:00 AM, 12/11/78 (WIL 4)

*See Instructions On Reverse Side

FROM: DISTRICT GEOLOGIST ME, SALT LAKE CITY, UTAH

TO: DISTRICT ENGINEER, O&G, SALT LAKE CITY, UTAH

SUBJECT: APD MINERAL EVALUATION REPORT

LEASE NO. U-022070-AOPERATOR: CIG Exploration, Inc.WELL NO. CIGE 34-13-10-20LOCATION: NE $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$ sec. 13, T. 10S., R. 20E., SLMUintah County, Utah

1. Operator predicted stratigraphy and predicted hydrocarbon zones are adequate? yes.
If not, USGS predictions are:

2. Fresh water aquifers probable below surface casing? No.

3. Other probable leasable minerals? Oil shale within the Green River (1350 - 4550').

4. Are hazardous fluids or gases likely? No.

5. Are abnormal conditions of pressure or temperature likely? No.

6. Will any strata penetrated need special mud, casing, or cementing beyond that proposed in the APD? No.

7. Is additional logging or sampling needed? Make sure program (CNL-FDC) is pulled through Green River rocks (1350 - 4550').

8. References - remarks: USGS Files, Salt Lake City, Utah

Is location within 2 miles of a KGS? Within the Bitter Creek KGS

Signature: Donald C. AlfordDate: 10 - 11 - 78

United States Department of the Interior
Geological Survey
8440 Federal Building
Salt Lake City, Utah 84138

Usual Environmental Analysis

Lease No. U-022070-AOperator CIG Exploration Co.Well No. CIGE 34-13-10-20Location NW SW NE 1823' FNL & 2090' FEL Sec. 13 T. 10 S. R. 20 E.County Uintah State Utah Field Bitter CreekStatus: Surface Ownership Public Minerals FederalJoint Field Inspection Date 10-4-78

Participants and Organizations:

Lynn HensonUSGSSteve EllisBLMGary HatchCIG

Related Environmental Analyses and References:

- (1) Unit Resource Analysis Seep Ridge Planning Unit (08-02)
BLM, Vernal, Utah
- (2)

*Pad 250 x 375
Pit 50 x 100
0.4 mi new access
Stockpile disposal
200*

Analysis Prepared by: Lynn Henson, Petroleum Tech., Salt Lake City

Date 10/5/78Reviewed by George Diwachak, Env. Scientist
Salt Lake CityNoted - G. Diwachak

Proposed Action:

On September 25, 1978, CIG Exploration Company filed an Application for Permit to Drill the No. CIGE 34-13-10-20 development well, a 6,800-foot oil and gas test of the Wasatch Formation; located at an elevation of 5,098 ft. in the NW SW NE sec. 13, T. 10 S., R. 20 E., on Federal mineral lands and Public surface; Lease No. U-022070-A. There was no objection raised to the access nor to the access road.

A rotary rig would be used for the drilling. An adequate casing and cementing program is proposed. Fresh-water sands and other mineral-bearing formations would be protected. A Blowout Preventer would be used during the drilling of the well. The proposed pressure rating should be adequate. Details of the operator's NTL-6 10-Point Subsurface and 13-Point Surface Protection Plans are on file in the U.S.G.S. District Office in Salt Lake City, Utah, and the U.S.G.S. Northern Rocky Mountain Area Office in Casper, Wyoming.

A working agreement has been reached with the Bureau of Land Management, the controlling surface agency. Rehabilitation plans would be decided upon as the well neared completion; the Surface Management Agency would be consulted for technical expertise on those arrangements.

The operator proposes to construct a drill pad 250 ft. wide x 375 ft. long, and a reserve pit 100 ft. wide x 50 ft. long. A new access road would be constructed 18' ft. wide x 0.4 mi. long from an existing and improved road. The operator proposes to construct production facilities on a disturbed area of the proposed drill pad. If production is established, plans for a gas flow line would be submitted to the appropriate agencies for approval. The anticipated starting date is November 15, 1978, and duration of drilling activities would be about 25 days.

Location and Natural Setting:

The proposed drillsite is approximately 15 mi. SE of Ouray, Utah, the nearest town. A good road runs to within 3/10 mi. of the location. This well is in the Bitter Creek field.

Topography:

Rolling hills.

Geology:

The surface geology is Uinta formation. The soil is clays and sands.

No geologic hazards are known near the drillsite. Seismic risk for the area is minor. Anticipated geologic tops are filed with the 10-Point Subsurface Protection Plan.

Approval of the proposed action would be conditioned that adequate and sufficient electric/radioactive/density logging surveys would be made to locate and identify any potential mineral resources. Production casing and cementing would be adjusted to assure no influence of the hydrocarbon zones through the well bore on these minerals. In the event the well is abandoned, cement plugs will be placed with drilling fluid in the hole to assure protection of any mineral resources.

The potential for loss of circulation would exist. Loss of circulation may result in the lowering of the mud levels which might permit exposed upper formations to blowout or to cause formation to slough and stick to drill pipe. A loss of circulation would result in contamination due to the introduction of drilling muds, mud chemicals, filler materials, and water deep into the permeable zone, fissures, fractures, and caverns within the formation in which fluid loss is occurring. The use of special drilling techniques, drilling muds, and lost circulation materials may be effective in controlling lost circulation.

A geologic review of the proposed action has been furnished by the Area Geologist, U.S. Geological Survey, Salt Lake City, Utah. The operator's drilling, cementing, casing, and blowout prevention programs have been reviewed by the Geological Survey engineers and determined to be adequate.

Soils:

No detailed soil survey has been made of the project area. The top soils in the area range from a sandy clay to a clay-type soil. The soil is subject to runoff from rainfall and has a high runoff potential, and sediment production would be high. The soils are mildly to moderately alkaline and support the salt-desert shrub community.

Top soil would be removed from the surface and stockpiled. The soil would be spread over the surface of disturbed areas when abandoned to aid in rehabilitation of the surface. Rehabilitation is necessary to prevent erosion and encroachment of undesired species on the disturbed areas. The operator proposes to rehabilitate the location and access roads per the recommendations of the Bureau of Land Management.

Approximately two acres of land would be stripped of vegetation. This would increase the erosional potential. Proper construction practice, construction of water bars, and reseeding of slope-cut area would minimize this impact.

Air:

No specific data on air quality is available at the proposed location. There would be a minor increase in air pollution due to emissions from

rig and support traffic engines. Particulate matter would increase due to dust from travel over unpaved dirt roads. The potential for increased air pollution due to leaks, spills, and fire would be possible.

Relatively heavy traffic would be anticipated during the drilling operations phase, increasing dust levels and exhaust pollutants in the area. If the well was to be completed for production, traffic would be reduced substantially to a maintenance schedule with a corresponding decrease of dust levels and exhaust pollutants to minor levels. If the project results in a dry hole, all operations and impact from vehicular traffic would cease after abandonment. Due to the limited number of service vehicles and limited time span of their operation, the air quality would not be substantially reduced.

Toxic or noxious gases would not be anticipated.

Precipitation:

Annual rainfall should range from about 8 to 11 inches at the proposed location. The majority of the numerous drainages in the surrounding area are of a nonperennial nature flowing only during early spring runoff and during extremely heavy rain storms. This type of storm is rather uncommon as the normal annual precipitation is around 8 inches.

Winds are medium and gusty, occurring predominantly from West to East. Air mass inversions are rare.

The climate is semiarid with abundant sunshine, hot summers and cold winters, with temperature variations on a daily and seasonal basis.

Surface-Water Hydrology:

The White River is 17 mi. west. Cotton Wood Wash runs from the location to the White River.

Some additional erosion would be expected in the area since surface vegetation would be removed. If erosion became serious, drainage systems such as water bars and dikes would be installed to minimize the problem. The proposed project should have minor impact on the surface-water systems.

The potentials for pollution would be present from leaks or spills. The operator is required to report and clean up all spills or leaks.

Ground-Water Hydrology:

Some minor pollution of ground-water systems would occur with the introduction of drilling fluids (filtrate) into the aquifer. This is normal and unavoidable during rotary drilling operations. The potential for communication, contamination, and commingling of formations via the well bore would be possible. The drilling program is designed to prevent this. There is need for more data on hydrologic systems in the area and the drilling of this well may provide some basis information as all shows of fresh water would be reported. Water production with the gas would require disposal of produced water per the requirements of NTL-2B.

The depths of fresh-water formations are listed in the 10-Point Sub-surface Protection Plan. There would be no tangible effect on water migration in fresh-water aquifers. The pits would be unlined. If fresh water should be available from the well, the owner or surface agency may request completion as a water well if given approval.

Vegetation:

Sagebrush and native grass.

Plants in the area are of the salt-desert-shrub types.

Proposed action would remove about two acres of vegetation. Removal of vegetation would increase the erosional potential and there would be a minor decrease in the amount of vegetation available for grazing.

The operator proposes to rehabilitate the surface upon completion of operations.

Wildlife:

Animal and plant inventory has been made by the Bureau of Land Management. No endangered plants or animals are known to habitat on the project area. The fauna of the area consists predominantly of the mule deer, coyotes, rabbits, and varieties of small ground squirrels and other types of rodents and various types of reptiles. The area is used by man for the primary purpose of grazing domestic livestock and sheep. The birds of the area are raptors, finches, ground sparrows, magpies, crows, and jays.

Social-Economic Effect:

An on the ground surface archaeological reconnaissance would be required prior to approval of the proposed action. Appropriate clearances would then be obtained from the surface managing agency. If an historic artifact, an archaeological feature or site is discovered during construction operations, activity would cease until the extent, the scientific importance, and the method of mitigating the adverse effects could be determined by a qualified cultural resource specialist.

There are no occupied dwellings and other facilities of this nature in the general area. Minor distractions from aesthetics would occur over the lifetime of the project and are judged to be minor. All permanent facilities placed on the location would be painted a light sand color to blend in with the natural environment. Present use of the area is grazing, recreation, and oil and gas activities.

Noise from the drilling operation may temporarily disturb wildlife and people in the area. Noise levels would be moderately high during drilling and completion operations. Upon completion, noise levels would be infrequent and significantly less. If the area is abandoned, noise levels should return to predrilling levels.

The site is visible from any major roads. After drilling operations, completion equipment would not be visible to passersby of the area and would not present a major intrusion.

The economic effect of one well would be difficult to determine. The overall effect of oil and gas drilling and production activity are significant in Uintah County, Utah.

But should this well discover a significant new hydrocarbon source, local, state, and possibly national economics might be improved. In this instance, other development wells would be anticipated, with substantially greater environmental and economic impacts.

Should the wellsite be abandoned, surface rehabilitation would be done according to the surface agency's requirements and U.S. Geological Survey's satisfaction. This would involve leveling, contouring, reseeding, etc., of the location and possibly the access road. If the well should produce hydrocarbons, measures would be undertaken to protect wildlife and domestic stock from the production equipment.

There are no national state, or local parks, forests, wildlife refuges or ranges, grasslands, monuments, trails or other formally designated recreational facilities near the proposed location.

The proposed location is within the Seep Ridge Planning Unit (0802). This Environmental Assessment Record was compiled by the Bureau of

Land Management, the surface management agency of the Federal surface in the area. The study includes additional information on the environmental impact of oil and gas operations in this area and gives land use recommendations. The EAR is on file in the agency's State offices and is incorporated herein by reference.

Waste Disposal:

The mud and reserve pits would contain all fluids used during the drilling operations. A trash pit would be utilized for any solid wastes generated at the site and would be buried at the completion of the operations. Sewage would be handled according to State sanitary codes. For further information, see the 13-Point Surface Plan.

Alternatives to the Proposed Action:

(1) Not approving the proposed permit -- The oil and gas lease grants the Lessee exclusive right to drill for, mine, extract, remove, and dispose of all oil and gas deposits.

Under leasing provisions, the Geological Survey has an obligation to allow mineral development if the environmental consequences are not too severe or irreversible. Upon rehabilitation of the site, the environmental effects of this action would be substantially mitigated, if not totally annulled. Permanent damage to the surface and subsurface would be prevented as much as possible under the U.S. Geological Survey and other controlling agencies' supervision with rehabilitation planning reversing almost all effects. Additionally, the growing scarcity of oil and gas should be taken into consideration. Therefore, the alternative of not proceeding with the proposed action at this time is rejected.

(2) Minor relocation of the wellsite access road or any special restrictive stipulations or modifications to the proposed program would not significantly reduce the environmental impact. There are no severe vegetative, animal, or archaeological-historical-cultural conflicts at the site. Since only a minor impact on the environment would be expected, the alternative of moving the location is rejected. At abandonment, normal rehabilitation of the area such as contouring, reseeding, etc., would be undertaken with an eventual return to the present status as outlined in the 13-Point Surface Plan.

Adverse Environmental Effects Which Cannot Be Avoided:

Surface disturbance and removal of vegetation from approximately two acres of land surface from the lifetime of the project which would



CIG-EXPL.CO. U-822070-A
WELL #CIGE 34-15-10-20
NWSWNE-SEC.13-10S-20E
BITTER CREEK FIELD - UTAH

L


would be eliminated in the disturbed areas and there would be a minor and temporary disturbance of wildlife and livestock. Minor induced air pollution due to exhaust emissions from rig engines of support traffic engines would occur. Minor increase in dust pollution would occur due to vehicular traffic associated with the operation. If the well is a gas producer, additional surface disturbance would be required to install production pipelines. The potential for fires, leaks, spills of gas, oil, or water would exist. During the construction and drilling phases of the project, noise levels would increase. Potential for sub-surface damage to fresh-water aquifers and other geologic formations exists. Minor distractions from aesthetics during the lifetime of the project would exist. If the well is a producer, an irreplaceable and irretrievable commitment of resources would be made. Erosion from the site would eventually be carried as sediment in the White River. The potential for pollution to the Cottonwood Wash would exist through leaks and spills.

Determination:

This requested action does not constitute a major Federal action significantly affecting the environment in the sense of NEPA, Section 102(2)(C).

Date

11/2/78


District Engineer
U.S. Geological Survey
Conservation Division
Oil and Gas Operations
Salt Lake City District

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

BLM-SURFACE

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☒

OTHER

SINGLE
ZONE ☒MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

CIG EXPLORATION, INC.

3. ADDRESS OF OPERATOR

P. O. BOX 749, DENVER, CO 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)*

At surface

1823' FNL & 2090' FEL, Section 13, T10S, R20E

At proposed prod. zone

SAME AS ABOVE

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

APPROXIMATELY 15 MILES SOUTHEAST OF OURAY, UTAH

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drig. unit line, if any)

550'

16. NO. OF ACRES IN LEASE

2002.77

17. NO. OF ACRES ASSIGNED
TO THIS WELL

N/A

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED, APPROXIMATELY
OR APPLIED FOR, ON THIS LEASE, FT.

3000'

19. PROPOSED DEPTH

6800'

20. ROTARY OR CABLE TOOLS

ROTARY

21. ELEVATIONS (Show whether DP, RT, GR, etc.)

5098'

UNGRADED GROUND

22. APPROX. DATE WORK WILL START*

NOVEMBER 15, 1978

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	9-5/8"	36#	200'	125 sx
7-7/8"	4-1/2"	11.6#	6800'	CIRCULATE CEMENT BACK TO SURFACE

FRESH WATER AQUIFERS WILL BE PROTECTED WHEN THE LONG STRING IS RUN AND CEMENT IS
CIRCULATED TO SURFACE.

SEE ATTACHED SUPPLEMENTS FOR FURTHER INFORMATION:

- (1) 10-POINT PROGRAM
- (2) BOP SCHEMATIC
- (3) 13-POINT PROGRAM
- (4) PLAT

GAS WELL PRODUCTION HOOKUP TO FOLLOW ON SHUT-IN NOTICE


APPROVED BY THE DIVISION OF
OIL, GAS, AND MINING

DATE: 10-3-78

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED



TITLE

DISTRICT SUPERINTENDENT

DATE September 22, 1978

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

TITLE

DATE


CONDITIONS OF APPROVAL, IF ANY:

T10S, R20E, S.L.B. & M.

PROJECT

C.I.G. EXPLORATION INC.

Well location, *C.I.G.E. #34-13-10-20*, located as shown in the SW 1/4 NE 1/4 Section 13, T10S, R20E, S.L.B. & M. Uintah County, Utah.



C.I.G.E. #34-13-10-20
Elev. Ungraded Ground - 5098'

13



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

[Signature]
 REGISTERED LAND SURVEYOR
 REGISTRATION NO 2454
 STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING
 P O. BOX Q ~ 110 EAST - FIRST SOUTH
 VERNAL, UTAH - 84078

SCALE 1" = 1000'	DATE 9/18/78
PARTY DA SS DS JB SH DJ	REFERENCES GLO Plat
WEATHER Dry & Windy	FILE C.I.G.E.

X = Section Corners Located


C.I.G. EXPLORATION, INC.
C.I.G.E. #34-13-10-20

TOPO.

MAP 'A'



SCALE: 1" = 4 Mi.



CIGE 34-13-10-20
Section 13, T10S, R20E
Uintah County, Utah

10-POINT PROGRAM

1. Geologic name of surface formation:

UINTA

2. The estimated tops of important geologic markers:

GREEN RIVER 1350'

WASATCH 4550'

3. The estimated depths at which anticipated water, oil, gas are expected to be encountered:

WASATCH — 4550' — GAS

4. The proposed casing program, including the size, grade, and weight per foot each string and whether new or used:

9-5/8" - K-55, ST&C - 36# NEW

4-1/2" - N-80, LT&C - 11.6# NEW

5. The Operators' minimum specifications for pressure control equipment which is to be used, a schematic diagram thereof showing sizes, pressure ratings, and testing procedures and testing frequency:

Bottom:

3000# BOP W/4-1/2" pipe rams
3000# BOP W/blind rams
3000# Hydril

Top:

Grant rotating head

Manifold includes appropriate valves, positive and adjustable chokes and kill line to control abnormal pressures.

BOP's will be tested at installation and will be cycled on each trip.

6. The type and characteristics of the proposed circulating medium to be employed for rotary drilling and the quantities and types of mud and weighting material to be maintained:

6. Continued --

The well will be drilled with fresh water from surface to 4500' with a weight of 8.3 to 8.7 . From 4500' to TD the well will be drilled with fresh wtr mud with a weight from 8.7 to 10.4 . Sufficient weighting material (barite) will be on location to increase the mud weight if abnormal pressure is encountered.

7. The auxiliary equipment to be used:
- a. kelly cock
 - b. monitoring equipment on the mud system
 - c. a sub on the floor with a full opening valve to be stabbed into the drill pipe when the kelly is not in the string.

8. The testing, logging and coring program to be followed:
- No DST's are planned
 - No cores are expected to be cut.

LOGS: Dual Induction Laterolog
Compensated Neutron-Formation Density

9. Any anticipated abnormal pressures or temperatures expected to be encountered:
- No abnormal pressures or temperatures expected
 - No hydrogen sulfide expected


10. The anticipated starting date and duration of the operation:

November 15, 1978

Three week duration.

3000 psi

psi Working Pressure BOP's



Test Procedure

- 1) Flush BOP's and all lines to be tested with water.
- 2) Run test plug on test joint and seat in casing head (leave valve below test plug open to check for leak).
- 3) Test the following to rated pressure:
 - a) inside blowout preventer
 - b) lower kelly cock
 - c) upper kelly cock
 - d) stand pipe valve
 - e) lines to mud pump
 - f) kill line to BOP's
- 4) Close and test pipe rams to rated pressure.
- 5) Close and test Hydril to rated pressure.
- 6) Back off and leave test plug in place. Close and test blind rams to rated pressure.
- 7) Test all choke manifold valves to rated pressure.
- 8) Test kill line valves to rated pressure.

C.I.G. EXPLORATION INCORPORATED

13 Point Surface Use Plan

for

Well Location

C.I.G.E. #34-13-10-20

Located In

Section 13, T10S, R20E, S.L.B. & M.

1. EXISTING ROADS

See attached Topographic Map "A".

To reach C.I.G. Exploration Incorporated, well location C.I.G.E. #34-13-10-20 located in the SW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 13, T10S, R20E, S.L.B. & M., Uintah County, Utah; proceed Westerly out of Vernal, Utah along U.S. Highway 40, 14 miles to the junction of this road and Utah State Highway 209; proceed South along Utah State Highway 209, 7 miles more or less to the junction of this Highway and Utah State Highway 88; proceed South along Utah State Highway 88, 10 miles to Ouray, Utah; proceed on South along a county road known as the Seep Ridge Road + 11.4 miles to its junction with an oil field service road to the East; proceed Easterly along this road 0.4 miles to the point that the planned access road (discussed in Item #2) leaves the existing road and proceeds in a Southerly direction to the proposed location site in said Section 13.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to Ouray, Utah at which point the County road is surfaced with native asphalt for + 4 miles and then is a gravel surface to the aforementioned service road.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the areas they are located in and range from clays to a sandy-clay shale material.

There is no anticipated construction on any portion of the above described roads. They will meet the necessary standards required to facilitate an orderly flow of traffic during the drilling phase, completion phase, and production phase of this well at such time that production is established.

The roads that are required for access during the drilling phase, completion phase, and production phase of this well will be maintained at the standards required by the B.L.M. or other controlling agencies.

2. PLANNED ACCESS ROAD

See Topographic Map "B".

The proposed access road leaves the existing service road described in Item #1 in the NW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 13, T10S, R20E, S.L.B. & M., and proceeds in a Southerly direction approximately 0.3 miles to the proposed location site in said Section 13.

In order to facilitate the anticipated traffic flow necessary to drill and produce this well, the following standards will be met:

The proposed access road will be an 18' crown road (9' either side of the centerline) with drain ditches along either side of the proposed road where it is determined necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area.

Back slopes along the cut areas of the road will be 1 $\frac{1}{2}$ to 1 slopes and terraced.

The road will be centerline flagged prior to the commencement of construction.

2. PLANNED ACCESS ROAD - continued

The grade of this road will vary from flat to 8%, but will not exceed this amount. This road will be constructed from native borrow materials accumulated during construction.

If deemed necessary by the local governmental agencies or their representatives, turnouts will be installed for safety purposes every 0.25 miles or on the top of ridges or at intervals and locations that will provide the greatest sight distance. These turnouts will be 200' in length and 10' in width and will be tapered from the shoulder of the road for a distance of 50' in length at both the access and outlet ends.

Any fences that are encountered along this access road will be cut and replaced with a cattleguard having a minimum width of 18' and a loading factor large enough to facilitate the heavy trucks required in the drilling and production of this well.

If cattleguards are to be located at existing gates, they will be installed with the above requirements and with a new gate installed at one end of the cattleguard.

The access from the road to the gate will be of such a nature that there will be no impedance of traffic flow along the main access road and no difficulties encountered by traffic utilizing the gate, either leaving or entering the proposed access road.

The terrain that this road traverses is relatively flat and is broken with a few small hills and washes.

The vegetation along this route consists of sparse amounts of sagebrush, rabbit-brush, some grasses, and cacti with large areas that are devoid of vegetation.

3. LOCATION OF EXISTING WELLS

There are other wells within a one mile radius of this well. For exact location of this well within Section 13, T10S, R20E, S.L.B. & M., see location plat.

4. LOCATION OF TANK BATTERIES, PRODUCTION FACILITIES AND PRODUCTION GATHERING AND SERVICE LINES

At the present time there are other C.I.G. Exploration Incorporated batteries, production facilities, oil gathering lines, gas gathering lines, injection, and disposal lines within a one-mile radius.

In the event production of this well is established, the existing area of the location will be utilized for the establishment of the necessary production facilities.

This area will be built, if possible, with native materials and if these materials are not available then the necessary arrangements will be made to get them from private sources.

The total area that is needed for the production of this well will be fenced and cattleguards will be utilized for access to these facilities.

The proposed gas flow line will be an 18' right of way which will run in a North-easterly direction approximately 950' to an existing above ground pipeline at a point located in the NW $\frac{1}{4}$ NE $\frac{1}{4}$ Section 13, T10S, R20E, S.L.B. & M., (See Topographic Map "B").

If there is any deviation from the above, all appropriate agencies will be notified.

5. LOCATION OF AND TYPE OF WATER SUPPLY

Water to be used in the drilling of this well will be hauled from Willow Creek at the point where Hill Creek Road crosses it in the SE $\frac{1}{4}$ Section 5, T10S, R20E, S.L.B. & M. This water will be hauled by truck over existing roads and the proposed access road + 6.5 miles to the proposed location site.

In the event that the above source is not used, the water will be hauled by truck utilizing roads described in Items #1 and #2, from the White River South of Ouray, Utah a distance of + 10 road miles.

All regulations and guidelines will be followed and no deviations will be made unless all concerned agencies are notified.

6. SOURCE OF CONSTRUCTION MATERIAL

All construction material for this location site and access road shall be borrow material accumulated during construction of the location site and access road. No additional road gravels or pit lining material from other sources are anticipated at this time, but if they are required, the appropriate actions will be taken to acquire them from private sources.

The native material that will be used in the construction of this location site and access road will consist of a sandy-clay soil and sandstone and shale material gathered in actual construction of the road and location.

7. METHODS FOR HANDLING WASTE DISPOSAL

A reserve and burn pit shall be constructed and at least one half of the depth of the reserve pit shall be below the existing ground surface. All trash and flammable material will be burned in the burn pit. Non-flammable material such as cuttings, salts, chemicals, etc., will be buried in the reserve pit and covered with a minimum of four feet of earth material. Prior to the onset of drilling, the burn pit will be fenced on all four sides with a net wire, and the reserve pit will be fenced on three sides. Upon completion of drilling, the fourth side of the reserve pit will be fenced and allowed to dry completely before backfilling and reclamation are attempted. A portable chemical toilet will be supplied for human waste.

8. ANCILLARY FACILITIES

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. WELL SITE LAYOUT

See attached Location Layout Sheet.

The B.L.M. District Manager shall be notified before any construction begins on the proposed location site and road.

As mentioned in Item #6, the pits shall be unlined unless it is determined by the representatives of the agencies involved that the materials are too porous and would cause contamination to the surrounding area; then the pits will be lined with a gel and any other type of material necessary to make it safe and tight.

When drilling activities commence, all work shall proceed in a neat and orderly sequence.

10. PLANS FOR RESTORATION OF SURFACE

As there is some topsoil on the location site, all topsoil shall be stripped and stockpiled. (See Location Layout Sheet). When all drilling and production activities have been completed, the location site and access road will be reshaped to the original contour and stockpiled topsoil spread over the disturbed area. Fences around pits are to be removed upon completion of drilling activities and all waste being contained in the trash pit shall be buried with a minimum of 4' cover. The reserve pit will be completely fenced and allowed to dry before covering. When restoration activities have been completed the location site and access ramp shall be reseeded with a seed mixture recommended by the B.L.M. District Manager when the moisture content of the soil is adequate for germination. The Lessee further covenants and agrees that all of said cleanup and restoration activities shall be done and performed in a diligent and most workmanlike manner and in strict conformity with the above mentioned Items #7 and #10.

11. OTHER INFORMATION

The Topography of the General Area - (See Topographic Map "A".)

The area slopes from the rim of the Book Cliff Mountains to the South to the Green River to the North, and is a portion of the Roan Plateau. The area is interlaced with numerous canyons and ridges which are extremely steep with numerous ledges formed in sandstones, conglomerates, and shale deposits.

The majority of the washes and streams in the area are non-perennial in nature with the only ones in the area having a year round flow being Willow Creek to the West, and the White and Green Rivers to the North, of which the numerous washes, draws, and non-perennial streams are tributaries to the White River.

The surrounding drainages are of a non-perennial nature with normal flow limited to the early spring run-off and heavy thunderstorms or rain storms of high intensity that last over an extended period of time and are rare in nature as the normal annual precipitation is only 8".

All drainages in the immediate area are non-perennial streams, flowing to the North, and are tributaries to the White River.

The soils of this semi-arid area are of the Uinta Formation and Duchesne River Formation (the Fluvial Sandstone and Mudstone) from the Eocene Epoch and Quaternary Epoch (gravels surfaces) and the visible geologic structure consists of light brownish-gray clays (OL) to sandy soils (SM-ML) with poorly graded gravels and shales with out crops of rock (sandstone, mudstone, conglomerates, and shales).

Due to the low precipitation average, climatic conditions, and the marginal types of soils, the vegetation that is found in the area is common of the semi-arid region we are located in and in the lower elevations of the Uinta Basin. It consists of , as primary flora, areas of sagebrush, rabbitbrush, some grasses, cacti, and large areas of bare soils devoid of any growth. In the areas away from and in the vicinity of non-perennial streams, and along the edges of perennial streams, cottonwoods, willows, tamarack, sagebrush, rabbitbrush, grasses, and cacti can be found.

The fauna of the area is sparse and consists predominantly of the mule deer, coyotes, pronghorn antelope, rabbits, varieties of small ground squirrels and other types of rodents, and various reptiles common to the area.

11. OTHER INFORMATION - continued

The birds of the area are raptors, finches, ground sparrows, magpies, crows and jays.

The area is used by man for the primary purpose of grazing domestic livestock.

The Topography of the Immediate Area - (See Topographic Map "B")

C.I.G.E. #34-13-10-20 location site sits on a relatively flat area in the bottom portion of a large draw, surrounded by numerous small hills. The proposed location site lies approximately 2 miles East of Willow Creek.

The geologic structure of the location is of the Uinta Formation and consists of light brownish-gray sandy clay (SP-CL) with some sandstone outcrops.

The ground slopes from the Southwest through the location to the Northeast at approximately a 4% grade.

The location is covered with some sagebrush and grasses.

There are no occupied dwellings or other facilities of this nature in the general area.

There are no visible archaeological, historical, or cultural sites within any reasonable proximity of the proposed location site. (See Topographic Map "B").

12. LESSEE'S OPERATOR'S REPRESENTATIVE

Frank R. Midkiff
C.I.G. Exploration Incorporated
P.O. Box 749
Denver, Colorado 80201

TELE: 1-303-572-1121


13. CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by C.I.G. Exploration Incorporated and its contractors and sub-contractors in conformity with this plan and the terms and conditions under which it is approved.

DATE


9/22/78

Frank R. Midkiff
District Manager



C.I.G. EXPLORATION

C.I.G.E. #34-13-10-20
LOCATION LAYOUT & CUT SHEET



FUEL


STORAGE

TOILET

FUEL

TRAILER

SOILS LITHOLOGY
- NO SCALE -




LIGHT BROWN SANDY CLAY (SC-ML)

SCALE - 1" = 50'

WIND EAST

SCALE 1" = 50'

CROSS SECTIONS



APPROX. YARDAGES

CUT - 9,315 CU. YDS.

FILL - 2,304 CU. YDS.

C.I.G.E. EXPLORATION, INC.

C.I.G.E. #34-13-10-20

TOPO. MAP 'B'



SCALE 1" = 2000'


ROAD CLASSIFICATION

Medium-duty

Light-duty

Unimproved dirt

○ State Route



UTAH

40 MILES TO
CURRY, UTAH

9 MILES TO
CURRY, UTAH

15 MILES TO
CURRY, UTAH

20 MILES TO
CURRY, UTAH

CIGE 35-1-10-20

BELCO

NB 27-1B

BELCO

NB 16-2-B

BELCO
NB 63-12-B

BELCO
NB 17-B

UNITAH 3

EXISTING
ROAD

CIGE 13-7-10-21

CIGE 27-18-10-21

PROPOSED
ACCESS
ROAD

PROPOSED LOCATION

C.I.G.E. #34-13-10-20

CIGE 12-5-10-21

BELCO
NB 29-5B

CIGE 7-8-10-21

BELCO
NB 18-8-B

BELCO
NB 7-9-B


NB 3

BELCO
NB 17-18-B

BELCO
NB 26-13-B

PROPOSED
WATER
SOURCE

MAPCO
11-F 15



STATE OF UTAH
DIVISION OF OIL, GAS, AND MINING

** FILE NOTATIONS **

Date: Oct. 2.

Operator: Cy Exploration

Well No: Natural Butte 37-13-10-20

Location: Sec. 13 T. 10S R. 20E County: Uintah

File Prepared: ☐

Entered on N.I.D.: ☐

Card Indexed: ☐

Completion Sheet: ☐

API Number: 43041-30508

CHECKED BY:

Administrative Assistant: [Signature]

Remarks: Unit Well ok R

Petroleum Engineer: [Signature]

Remarks:

Director: 7

Remarks:

INCLUDE WITHIN APPROVAL LETTER:

Bond Required: ☒

Survey Plat Required: ☐

Order No. _____

Surface Casing Change to ☐

Rule C-3(c), Topographic exception/company owns or controls acreage within a 660' radius of proposed site ☐

O.K. Rule C-3 ☐

O.K. In Nat Butte Unit

Other:

[Signature] Letter Written/Approved



ARCHEOLOGICAL - ENVIRONMENTAL RESEARCH CORPORATION

P.O. Box 17544 - Salt Lake City, Utah 84117

Tel.: (801) ~~582-0343~~ 486-0261

October 10, 1978

3A

55-201-9-21

Subject: Archeological Reconnaissance for Proposed
Well Locations and Associated Access Roads
in the Natural Buttes Locality of Uintah
County, Utah

Project: Gas Producing Enterprise - 1978 Gas-Oilwell
Development in Uintah County, Utah

Project No.: GPE-78-5A

Permit No.: 78-Ut-014

To: Mr. Karl Oden, Gas Producing Enterprise,
P. O. Box 1138, Vernal, Utah 84078

Ms. Maggie Dominy, CIG Exploration, 2100
Prudential Plaza, P. O. Box 749, Denver,
Colorado 80201

Mr. Dean Evans, BLM Area Manager, Bureau
of Land Management, Vernal District Office,
P. O. Box F, 91 West Main Street, Vernal,
Utah 84078

Mr. Lloyd Ferguson, District Manager,
Bureau of Land Management, Vernal District
Office, P. O. Box F, 91 West Main Street,
Vernal, Utah 84078

Info: Mr. Richard Fike, BLM Archeologist, Bureau
of Land Management, University Club Bldg.,
136 East South Temple, Salt Lake City,
Utah 84111

2. Legal Description of Project Area

BLM Surface and Subsurface

<u>Well #</u>	<u>Section</u>	<u>Township</u>	<u>Range</u>	<u>Access Road</u>
25	29	9 South	21 East	Same
26	26	10 South	21 East	Same
27	18	10 South	21 East	Same
30	6	10 South	21 East	Same
31	1	10 South	22 East	Same
33	27	10 South	21 East	Section 22 also
34	13	10 South	20 East	Same
35	1	10 South	20 East	Section 11 and 12 also
38	4	10 South	21 East	Section 5 also

Ute Indian Surface and BLM Subsurface

<u>Well #</u>	<u>Section</u>	<u>Township</u>	<u>Range</u>	<u>Access Road</u>
STATE — ✓ 19	16	9 South	21 East	Section 16 also
✓ 22	15	9 South	20 East	Same
28	21	9 South	20 East	Same
✓ 29	23	9 South	20 East	Same
32	20	9 South	20 East	Same
40	20	9 South	22 East	Section 19 also

DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
Moab District Office

Summary Report of
Inspection for Cultural Resources

BLM Use Only: Use Initials.
(Use File)

Report Acceptable Yes ___ No ___

Mitigation Acceptable Yes ___ No ___
Comments:

Project Name, Developer Archeological Reconnaissance for Proposed Well
Producing Enterprises Locations and Associated Access Roads in the Natural
Buttes Locality of Uintah County, Utah (GPE-78-5A)
Legal Description of Project Area (Attach Map Also)

See attached sheet

Institution Holding Antiquities
Museum of Ethnology and Archaeology
Brigham Young University; Provo, Utah

4. Antiquities Permit No.

78-Ut-014

Dates of Field Work

September 12 through 21, 1978

Description of Examination Procedures
Drill Pads: Parallel transects ca. 15 meters apart were performed. Each
transect extended at least 15 meters beyond the marked boundaries of the pad.
Access Roads: Two parallel transects were performed for each access road;
each ca. 15 meters apart. In this manner a corridor ca. 30 meters (98 feet)
wide was examined.

Description of Findings (Attach forms or detailed report, if appropriate)

No cultural resource sites were discovered during the performance of the
surface reconnaissance.

Actual/Potential National Register Properties Affected
The National Register of Historic Places was consulted. No National Register
properties will be affected by the activities described above.


Conclusions/Recommendations 1. All vehicular traffic, personnel movement, and
construction be confined to the locations examined and to access roads leading
into these locations; 2. all personnel refrain from collecting individual
artifacts or from disturbing any cultural resources in the area; and 3. a
qualified archeologist be consulted should cultural remains from subsurface
deposits be exposed during construction work or if the need arises to relocate
or otherwise alter the construction site.

Signature of Person in Direct Charge of Field Work

Dennis G. Weder

Signature of Title of Institutional Officer Responsible

JR + [unclear]



T. 10S.

R. 20 & 21E.

Meridian: Salt Lake B & M

Quad:

Project: GPE-78-5

Series: Eastern Utah

Date: 10/10/78


PROPOSED WELL LOCATION AND
ACCESS ROAD
CIGE 34-13-10-20
NATURAL BUTTES LOCALITY
UINTAH COUNTY, UTAH

Big Pack Mtn. NE,
Utah
7.5' Series

Legend:

Proposed Well Location

Proposed Access Road ----



Scale

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE-
(Other Instructions
reverse side)Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

U-022070-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☐ GAS WELL ☒ OTHER

2. NAME OF OPERATOR

GAS PRODUCING ENTERPRISES, INC.

3. ADDRESS OF OPERATOR

P. O. BOX 749, DENVER, CO 80202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)

See also space 17 below.
At surface

1823' FNL & 2090' FEL SECTION 13-T10S-R20E

14. PERMIT NO.

43-047-30508

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

5098'

UNGRADED GROUND

12. COUNTY OR PARISH

UINTAH

13. STATE

UTAH

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

PIPELINE HOOKUP

X

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

PIPELINE HOOKUP

(Note: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

X

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

SUPPLEMENT TO APPLICATION FOR PERMIT TO DRILL

- (1) PROPOSED GAS WELL PRODUCTION HOOKUP
- (A) TYPICAL WELL HEAD INSTALLATION
- (B) TYPICAL MAIN LINES AND PIPE ANCHOR DETAIL
- (2) PROPOSED PIPELINE MAP
- (3) PROPOSED ROAD FOR FLOW LINE AND PIPELINE RIGHT OF WAY

FOR ON-SITE CONTACT:

EDWARD N. NORRIS AT (801) 789-2773

OR

IRA K. McCLANAHAN AT (303) 473-2300

18. I hereby certify that the foregoing is true and correct

SIGNED

F. R. MIOKIEF

TITLE

DISTRICT SUPERINTENDENT

DATE

October 10, 1978


(This space for Federal or State office use)



APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:





Colorado Interstate Gas Co.
COLORADO SPRINGS COLORADO

TYPICAL CONNECTION TO MAIN LINES AND PIPE ANCHOR
DETAIL - NATURAL BUTTES FIELD

UINTA COUNTY, UTAH

1 23858 REVISE STARTING POINT 8-27-77 RWP

NO.	C.O. NO.	DESCRIPTION	DATE	BY	CHK.	APP.

SCALE: NONE DRAWN RWP

DATE: 7-7-77

115FP-1 1/3

REVISIONS

23858

ESTIMATE SKETCH


DATE: 9/22/78
STARTING DATE: _____
EST. COMP. DATE: _____
☐ COMPANY ☒ CONTRACT

☒ COLORADO INTERSTATE GAS COMPANY
☐ NORTHWEST PIPELINE CORPORATION


W. O. NO.: _____
REVISION NO.: 11 9/28/78
BUDGET NO.: _____
RELATED DWG.: _____

LOCATION: 1307' FNL, 1419' FNL SEC. 6-10S-21E COUNTY: Uintah STATE: Utah
DESCRIPTION OF WORK: Connect C16E #30-6-10-21 Natural Buttes
Δ Connect C16E #34-13-10-20

REQUESTED BY: _____ APPROXIMATE MILEAGE: _____ PROJECT ENGINEER: _____



Freehand sketch of location of proposed installation to be constructed or retired showing relative location of existing facilities in area.



GAS PRODUCING ENTERPRISES, INC.
DENVER, COLORADO

CIGE 34-13-10-20
SECTION 13-T10S-R20E
UINTAH COUNTY, UTAH

September 29, 1978

Statement for permit to lay flow line, to be included with application for Drilling Permit - CIGE #34-13-10-20.

Upon approval of all concerned regulatory agencies, CIG proposed to install a surface flow line from CIGE #34-13-10-20 in a southwesterly direction through the west line of Section 6 and the SE $\frac{1}{4}$ of Section 1 connecting to a line (F65-2") from Belco #27-1B in the SE $\frac{1}{4}$ of Section 1 all in T10S, R20E and R21E. The line will be approximately 3,700' long as shown on the accompanying sketches.

Pipe will be 2-3/8" O.D. x .125" W.T., Grade X-42 EW. It will be butt-welded in place using portable electric welding machines, and will be laid above ground except where burial is necessary for road crossing, ditches, or other obstructions.

CIG will connect to Producer's separator and install dehydration and metering facilities within 100' of the connection.

Some damage will be incurred by trucks transporting pipe and welding equipment over the pipeline route, but surface disturbance will be held to a minimum.

DIVISION OF OIL, GAS, AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: CIG EXPLORATION

WELL NAME: CIGE 34-13-10-20

SECTION 13 TOWNSHIP 10S RANGE 20E , COUNTY Uintah

DRILLING CONTRACTOR Atco

RIG # not known at this time

SPUDDED: DATE April 14, 1979

TIME 6:30 p.m.

HOW dry hole spudder

DRILLING WILL COMMENCE not known at this time

REPORTED BY Pat Bohner

TELEPHONE #

DATE April 16, 1979

SIGNED M. J. Minner

cc: U. S. Geological Survey

NOTICE OF SPUD

WELL NAME: P 116E 34-13-10-20

LOCATION: SW 1/4 NE 1/4 SECTION 13 T- 10S R- 20E

COUNTY: Uintah STATE: Utah

LEASE NO.: U-022070-A LEASE EXPIRATION DATE: _____

UNIT NAME (If Applicable): NATURAL BUTTES Unit

DATE & TIME SPUDDED: 6:30 pm 4/14/79

DRY HOLE SPUDDER: Roberts Air Co

DETAILS OF SPUD (Hole, Casing, Cement, etc.): 12 1/4" hole to 204' GL.
RU E ran 5 jts 9 5/8", 36#, K-55 ST & C & Set @ 204' GL.
Cmt w/ 150 SX "6" + 2% CaCl₂ PD @ 11:00am 4/17/79

ROTARY RIG NAME & NUMBER: Atco # 5

APPROXIMATE DATE ROTARY MOVES IN: April 15th

FOLLOW WITH SUNDRY NOTICE

USGS CALLED: DATE: 4/16/79

PERSON CALLED: Mary

STATE CALLED: DATE: 4/16/79

PERSON CALLED: Linda

REPORTED BY: Pat Bohner

UNIT STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN TRIPlicate
(Other Instructions
on reverse side)

Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.
U-022070-A

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME
NATURAL BUTTES UNIT

8. FARM OR LEASE NAME
NATURAL BUTTES

9. WELL NO.
CIGE 34-13-10-20

10. FIELD AND POOL, OR WILDCAT
BITTER CREEK FIELD

11. SEC., T., R., N., OR BLK. AND
SURVEY OR AREA
SECTION 13-T10S-R20E

12. COUNTY OR PARISH
UINTAH

13. STATE
UTAH

1. OIL ☐ WELL GAS ☒ WELL OTHER

2. NAME OF OPERATOR
GAS PRODUCING ENTERPRISES, INC.

3. ADDRESS OF OPERATOR
P. O. BOX 749, DENVER, CO 80201

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

1823' FNL & 2090' FEL SECTION 13-T10S-R20E

14. PERMIT NO.
43-047-30508

15. ELEVATIONS (Show whether DF, RT, GR, etc.)
5098' UNGR. GR.

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
(Other) ☐

PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
ABANDON* ☐
CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐
FRACTURE TREATMENT ☐
SHOOTING OR ACIDIZING ☐
(Other) ☐

REPAIRING WELL ☐
ALTERING CASING ☐
ABANDONMENT* ☐
SPUD ☒

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.) *

CONFIRMATION OF VERBAL REPORT OF SPUD TO USGS (MARY) AND STATE (LINDA)
ON 4/16/79. PLEASE SEE ATTACHED.

18. I hereby certify that the foregoing is true and correct

SIGNED

R. G. Merrill
R. G. Merrill

TITLE Sr. Petroleum Engineer

DATE 4/19/79

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See instructions on
reverse side)Form approved.
Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL:		OIL WELL <input type="checkbox"/>	GAS WELL <input checked="" type="checkbox"/>	DRY <input type="checkbox"/>	Other <input type="checkbox"/>		
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	Other <input type="checkbox"/>
2. NAME OF OPERATOR		CIG Exp. Inc.					
3. ADDRESS OF OPERATOR		GAS PRODUCING ENTERPRISES, INC.					
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)*		P.O. BOX 749, DENVER, COLORADO 80201					
At surface		1823' FNL & 2090' FEL, Section 13-T10S-R20E					
At top prod. interval reported below		SAME					
At total depth		SAME					
14. PERMIT NO.		DATE ISSUED					
43-047-30508		10-3-78					
15. DATE SPUDDED	16. DATE T.D. REACHED	17. DATE COMPL. (Ready to prod.)	18. ELEVATIONS (DF, REB, RT, GR, ETC.)*	19. ELEV. CASINGHEAD			
4-14-79	5-13-79	6-4-79	5098' Ungr. Gr.	Unknown			
20. TOTAL DEPTH, MD & TVD	21. PLUG, BACK T.D., MD & TVD	22. IF MULTIPLE COMPL., HOW MANY*	23. INTERVALS DRILLED BY	ROTARY TOOLS	CABLE TOOLS		
6700'	6670'	N/A	→	205'-TD	0-205' GL		
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)*					25. WAS DIRECTIONAL SURVEY MADE		
6576'-5230' WASATCH					YES		
26. TYPE ELECTRIC AND OTHER LOGS RUN					27. WAS WELL CORED		
DIL, FDC-CNL					NO		
28. CASING RECORD (Report all strings set in well)							
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED		
9-5/8"	36#	205'	12-1/4"	150 SX			
4-1/2	11.6#	6700'	7-7/8"	2331 SX			
29. LINER RECORD			30. TUBING RECORD				
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
					NOT YET RUN		
31. PERFORATION RECORD (Interval, size and number)				32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
Perf w/2-1/8" csg gun w/1 JSPF @ 6576', 6574', 6572', 5948', 5946', 5941', 5494', 5485', 5480', 5476', 5470', 5461', 5236', 5234', 5230' (16 holes total)				DEPTH INTERVAL (MD)		AMOUNT AND KIND OF MATERIAL USED	
				Acidize w/3000 gals 7 1/2% acid w/30 RCN ball sealers. Flush w/151 bbls 2% KCl. Frac w/70,000 gals Apollo gel 40 & 150,000# 20/40 sand. Displ w/2% KCl wtr.			
33.* PRODUCTION							
DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
5-25-79		Flowing				SI - WO pipeline	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
6-3-79	24	19/64"	→	0	3000	5	---
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
---	1375	→	---	3000	5	---	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)						TEST WITNESSED BY	
Vented						K. E. Oden	
35. LIST OF ATTACHMENTS							
None							
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records							
SIGNED		TITLE			DATE		
F.R. Midkiff		District Superintendent			6-8-79		

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TRUE VERT. DEPTH
NO DST'S OR CORES.				Green River	1270'	
				Wasatch	4554'	

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☒ well other ☐
2. NAME OF OPERATOR
Coastal Oil & Gas Corporation
3. ADDRESS OF OPERATOR
P. O. Box 749, Denver, CO 80201
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1823' FNL & 2090' FEL
AT TOP PROD. INTERVAL: SAME
AT TOTAL DEPTH: SAME

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐

SUBSEQUENT REPORT OF:

☐
☐
☐
☐
☐
☐
☐
☐

(other) NTL-2B Unlined Pit

Approval Denied

5. LEASE
U-022070-A
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
N/A
7. UNIT AGREEMENT NAME
Natural Buttes Unit
8. FARM OR LEASE NAME
Natural Buttes
9. WELL NO.
CIGE 34-13-10-20
10. FIELD OR WILDCAT NAME
Natural Buttes Field
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Section 13-T10S-R20E
12. COUNTY OR PARISH
Uintah 13. STATE
Utah
14. API NO.
43-047-30508
15. ELEVATIONS (SHOW DF, KDB, AND WD)
5098' Ungr. Gr.

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

This application is to request approval to dispose of produced waters in an unlined pit with a bentonite seal. The subject well produces less than four BWPD. The attached water analysis gives the composition of produced waters. Water is produced from the Wasatch formation. The evaporation rate for the area compensated for annual rainfall is 70 inches per year. The percolation rate is 2-6 inches per hour for the area. The pit itself is 30' x 30' at the surface, tapering down to 25' x 25', having a depth of 6-1/2 feet. See the attached map for location of well site. The pit is located at the well site.


The areal extent and depth of waters containing less than 10,000 ppm TDS is unknown. The cement for the 4-1/2" casing is brought back near surface which protects all surface waters.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED F. R. Midkiff TITLE Production Superintendent DATE August 11, 1980
(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:



COLORADO INTERSTATE GAS COMPANY

STATE COPY

WELL TEST DATA FORM

FIELD CODE 560-01-11			FIELD NAME NATURAL BUTTES, UT			OPERATOR CODE 2200		OPERATOR NAME CIG EXPLORATION INC			WELL NAME CIGE 34-13-10-20		
WELL CODE 25425		SECT. 13		LOCATION TOWNSHIP/BLK 10S 20E		PANHANDLE/REDCAVE SEQ. NUMBER K-FACTOR		FORMATION WASATCH SA FLOW TEST					

WELL ON (OPEN)			DATE (COMP.)			ORIFICE SIZE		METER RUN SIZE		COEFFICIENT		GRAVITY (SEP.)		METER DIFF. RANGE		METER PRESSURE		DIFFERENTIAL ROOTS		METER TEMP		WELL HEAD TEMP		FLOWING TUBING PRESSURE		STATIC TUBING PRESSURE		FLOWING TUBING PRESSURE	
MO.	DAY	YR.	MO.	DAY	YR.																								
11-12	13-14	15-16	17-18	19-20	21-22	23	27-28	29-30	31-32	33-34	35-36	37-38	39-40	41-42	43-44	45-46	47-48	49-50	51-52	53-54	55-56	57-58	59-60	61-62	63-64	65-66	67-68	69-70	71-72
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX
1	31	84	02	07	84	00875	2.067	03824	0.574	100	00576	0820	085	007700	008240	X													

WELL-OFF (SHUT-IN)			SHUT-IN TEST			SLOPE		EFFECTIVE DIAMETER		EFFECTIVE LENGTH		GRAVITY (RAW GAS)		EST CSG PRESS		EST FSG PRESS		TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT	
MO.	DAY	YR.	MO.	DAY	YR.														
11-12	13-14	15-16	17-18	19-20	21-22	23	28-29	30-31	32-33	34-35	36-37	38-39	40-41	42-43	44-45	46-47	48-49	50-51	52-53
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX
02	07	84	02	10	84	01000	0	010350		700	4.0000	5903	0.574						

METER STAMP	25425		00875		REMARKS: 12 Choke	
-------------	-------	--	-------	--	----------------------	--

COLORADO INTERSTATE GAS COMPANY

STATE COPY

WELL TEST DATA FORM

WELL CODE 25425		SECT. 10		LOCATION TOWNSHIP/LK 10 30		RGE/SUR. 30		SEG. NUMBER		K-FACTOR		FORMATION Washakie		OPERATOR CODE 2200		OPERATOR NAME CIG E operation		WELL NAME CIG E 34-1840-20																							
WELL-ON (OPEN)		DATE (CONP.)						ORIFICE SIZE		METER RUN SIZE		COEFFICIENT		GRAVITY (SEP.)		METER DIFF. RANGE		METER PRESSURE		DIFFERENTIAL ROOTS		METER TEMP.		WELL HEAD TEMP.		FLOWING TBG/CSG PRESSURE		STATIC TBG/CSG PRESSURE		FLOWING STRING											
MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.						
11-12	13-14	15-16	17-18	19-20	21-22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52						
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX						
07	13	83	17	22	83	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875	00	875						
WELL-OFF (SHUT-IN)		SHUT-IN TEST						SLOPE		EFFECTIVE DIAMETER		EFFECTIVE LENGTH		GRAVITY (RAW GAS)		EST CSG PRESS		EST TBG PRESS		TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT.																					
MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.
11-12	13-14	15-16	17-18	19-20	21-22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52						
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX			
25425		00875		REMARKS:		extended 47 ft. on 10/13/83. No gas flow after extending test.														CIG:				OPERATOR: CL Webb				COMMISSION:													

COLORADO INTERSTATE GAS COMPANY

WELL TEST DATA FORM

STATE COPY

FIELD CODE			FIELD NAME										OPERATOR CODE		OPERATOR NAME										WELL NAME									
01-11			NATURAL BUTTES, UT										2200		CIG EXPLORATION INC										CIG 34-13-10-20									
CODE			LOCATION										PANHANDLE/REDCAVE		FORMATION																			
7			SECT. TOWNSHIP/BLK RGE/SUR.										SEQ. NUMBER		K-FACTOR																			
25425			13 10 20E												WASATCH SA FLOW TEST																			

WELL ON (OPEN)									DATE (COMP.)										ORIFICE SIZE		METER RUN SIZE		COEFFICIENT		GRAVITY (SEP.)		METER DIFF. RANGE		METER PRESSURE		DIFFERENTIAL ROOTS		METER TEMP.		WELL HEAD TEMP.		FLOWING TBG/CSG PRESSURE		STATIC TSG/CSG PRESSURE		FLOWING STRING						
MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.						
11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52						
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX			
06	08	83	06	15	83	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5

WELL-OFF (SHUT-IN)									SHUT-IN TEST										SLOPE		EFFECTIVE DIAMETER		EFFECTIVE LENGTH		GRAVITY (RAW GAS)		EST CSG PRESS		EST TBG PRESS		TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT.																						
MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.	MO.	DAY	YR.			
11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58						
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX			
06	15	83	06	15	83	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5	00	87	5

REMARKS:										CIG: <i>J. B. ...</i>									
25425 00875										OPERATOR: <i>Clayton L. Webb</i>									
										COMMISSION:									

WELL CODE 565-01-11			FIELD NAME NATURAL BUTTES, UT			OPERATOR CODE 2200			OPERATOR NAME CIG EXPLORATION INC			WELL NAME CIG 34-13-10-20																													
WELL CODE 3			LOCATION SECT. TOWNSHIP/BLK 25425 13 10 20E			PANHANDLE/REDCAVE SEQ. NUMBER K-FACTOR			FORMATION MORROW SAN FLOW TEST																																
WELL ON (OPEN)			DATE (COMP.)			ORIFICE SIZE			METER RUN SIZE			FLOW TEST																													
MO. DAY YR.			MO. DAY YR.			ORIFICE SIZE			METER RUN SIZE			FLOW TEST																													
11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-38 39-40 41-42 43-44 45-46 47-48 49-50 51-52 53-54 55-56 57-58 59-60 61-62 63-64 65-66 67-68 69-70 71-72 73-74 75-76 77-78 79-80 81-82 83-84 85-86 87-88 89-90 91-92 93-94 95-96 97-98 99-100			11-12 13-14 15-16 17-18 19-20 21-22 23-24 25-26 27-28 29-30 31-32 33-34 35-36 37-		

COLORADO INTERSTATE GAS COMPANY

WELL TEST DATA FORM

STATE COPY

FIELD CODE 560-01-11			FIELD NAME NATURAL HUTTES, UT			OPERATOR CODE 2210			OPERATOR NAME CIG EXPLORATION INC			WELL NAME CIG 560-01-11-01		
WELL CODE 25425			LOCATION SECT. 13 TOWNSHIP/BLK 10 RGE/SUR. 200			PANHANDLE/REDCAVE SEQ. NUMBER K-FACTOR			FORMATION MORROW SAND FLOW TEST					

WELL ON (OPEN)			DATE (COMP.)			ORIFICE SIZE			METER RUN SIZE			COEFFICIENT			GRAVITY (SEP.)			METER DIFF. RANGE			METER PRESSURE			DIFFERENTIAL ROOTS			METER TEMP.			WELL HEAD TEMP.			FLOWING TBG/CSG PRESSURE			STATIC TSG/CSG PRESSURE			FLOWING STRING		
MO.	DAY	YR.	MO.	DAY	YR.																																				
11	12	13	14	15	16	17	18	19	20	21	22	23	27	28	32	33	38	39	42	43	45	46	51	52	55	56	58	59	61	62	67	68	73	74	75						
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X						
06	15	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82	06	22	82			

WELL-OFF (SHUT-IN)			SHUT-IN TEST			SLOPE			EFFECTIVE DIAMETER			EFFECTIVE LENGTH			GRAVITY (RAW GAS)			EST CSG PRESS			EST TBG PRESS			TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT. CIG: <i>[Signature]</i> OPERATOR: <i>C. L. Wells</i> COMMISSION: _____														
MO.	DAY	YR.	MO.	DAY	YR.																																	
11	12	13	14	15	16	17	18	19	20	21	22	23	28	29	34	35	38	39	44	45	48	49	50	53	54	55												
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	E	E												
06	22	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82	06	25	82

STAMP			25425			00875			REMARKS: <i>Blow well on 7/20/80.</i>		
-------	--	--	-------	--	--	-------	--	--	---------------------------------------	--	--

COLORADO INTERSTATE GAS COMPANY

WELL TEST DATA FORM

STATE COPY

FIELD CODE 560-01-11			FIELD NAME NATURAL BUTTES			OPERATOR CIG			OPERATOR NAME CIG EXPLORATION INC			WELL NAME CIGE 34-13-10-20														
WELL CODE 25425			LOCATION SECT. 13 TWP. 10 RGE. 20E			FANHANDLE/REDCAVE SEQ. NUMBER			FORMATION MORROW SAN FLOW TEST			1														
WELL ON (OPEN)			DATE (COMP.)			ORIFICE SIZE			METER RUN SIZE			FLOW TEST														
MO.	DAY	YR.	MO.	DAY	YR.	SIZE	SIZE	COEFFICIENT	GRAVITY (SEP)	METER DIFF. RANGE	METER PRESSURE	DIFFERENTIAL ROOTS	METER TEMP.	WELL HEAD TEMP.	FLOWING TBG/CSG PRESSURE	STATIC TBG/CSG PRESSURE	FLOWING STRING TUBING	CASING								
11-12	13-14	15-16	17-18	19-20	21-22	23-24	25-26	27-28	29-30	31-32	33-34	35-36	37-38	39-40	41-42	43-44	45-46	47-48	49-50							
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X							
04	22	81	07	29	81	01	250	2	067	0	590	100	007220	01	70	084	07240	008300	X							
WELL-OFF (SHUT-IN)			SHUT-IN TEST			SLOPE			EFFECTIVE DIAMETER			EFFECTIVE LENGTH			GRAVITY (RAW GAS)			EST CSG PRESS			EST TBG PRESS			TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT.		
MO.	DAY	YR.	MO.	DAY	YR.	CASING PRESSURE (PSIG)	TUBING PRESSURE (PSIG)																			
11-12	13-14	15-16	17-18	19-20	21-22	23-24	25-26	27-28	29-30	31-32	33-34	35-36	37-38	39-40	41-42	43-44	45-46	47-48	49-50	51-52	53-54	55-56	57-58	59-60	61-62	
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	E	E					
06	15	81	06	18	81	008820	008820			700	4	0000	6700													
METER STAMP			25425			01250			REMARKS:																	

CIG: *J. B. B...*

OPERATOR: _____

COMMISSION: _____

COLORADO INTERSTATE GAS COMPANY

WELL TEST DATA FORM

STATE COPY

FIELD CODE 560-01-11			FIELD NAME NATURAL PUTTES				OPERATOR CODE 2200		OPERATOR NAME CIG EXPLORATION INC				WELL NAME CIGE 54-13-10-20																			
WELL CODE 56425		SECT. 13		LOCATION TWN/SH/BLK 10 20E		RGE/SUR. 20E		SEC. NUMBER		K-FACTOR		FORMATION MORROW SAN FLOW TEST																				
WELL ON (OPEN)			DATE (COMP.)				ORIFICE SIZE		METER RUN SIZE		COEFFICIENT		GRAVITY (SEP.)		METER DIFF. RANGE		METER PRESSURE		DIFFERENTIAL ROOTS		METER TEMP.		WELL HEAD TEMP.		FLOWING TBG/CSG PRESSURE		STATIC TBG/CSG PRESSURE		FLOWING STRING TUBING		CASING	
11-12	13-14	15-16	17-18	19-20	21-22	23	24-25	26-27	28-29	30-31	32-33	34-35	36-37	38-39	40-41	42-43	44-45	46-47	48-49	50-51	52-53	54-55	56-57	58-59	60-61	62-63	64-65	66-67	68-69	70-71	72-73	74-75
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX
02	25	80	09	12	80	01	232		057							100	00505.0	0570	70							66162	66128.0					
WELL-OFF (SHUT-IN)			SHUT-IN TEST				SLOPE		EFFECTIVE DIAMETER		EFFECTIVE LENGTH		GRAVITY (RAW GAS)		EST CSG PRESS		EST TBG PRESS		TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT.													
MO. DAY YR.			DATE			CASING PRESSURE (PSIG)		TUBING PRESSURE (PSIG)																								
11-12	13-14	15-16	17-18	19-20	21-22	23	24-25	26-27	28-29	30-31	32-33	34-35	36-37	38-39	40-41	42-43	44-45	46-47	48-49	50-51	52-53	54-55	56-57	58-59	60-61	62-63	64-65	66-67	68-69	70-71	72-73	74-75
XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	XX	E	E								
11	12	80	09	25	80	01	108		110				700	4	0000	5903																
METER STAMP			25425 01556										REMARKS:																			

COLORADO INTERSTATE GAS COMPANY

WELL TEST DATA FORM

STATE COPY

FIELD CODE			FIELD NAME			OPERATOR CODE			OPERATOR NAME			WELL NAME		
CODE			LOCATION			FACILITY/RESCAVE			FORMATION			WELL NAME		
SECT.			TWN/BLK			RGE/SUR.			SEQ. NUMBER			K-FACTOR		
13			105			206			WASATCH			C.I.G. # 34		

WELL ON (OPEN)						FLOW TEST																													
DATE (COMP.)						ORIFICE SIZE		METER RUN SIZE		COEFFICIENT		GRAVITY (SEP.)		METER DIFF. RANGE		METER PRESSURE		DIFFERENTIAL ROOTS		METER TEMP.		WELL HEAD TEMP.		FLOWING TBG/CSG PRESSURE		STATIC TSG/CSG PRESSURE		FLOWING STRING TUBING		CASING					
MO.	DAY	YR.	MO.	DAY	YR.	SIZE	SIZE																												
11	12	13	14	15	16	17	18	19	20	21	22	23	27	28	32	33	38	39	42	43	48	49	51	52	56	57	58	59	61	62	67	68	73	74	75
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	
10	16	79	11	17	79	01	000	12	067	050	73	0	100	106	92	0	7	65	079	019	78	0													

WELL-OFF (SHUT-IN)			SHUT-IN TEST										SLOPE		EFFECTIVE DIAMETER		EFFECTIVE LENGTH		GRAVITY (RAW GAS)		EST CSG PRESS		EST TBG PRESS		TO THE BEST OF MY KNOWLEDGE THE ABOVE DATA IS CORRECT.		
PRESSURE TAKEN			DATE		CASING PRESSURE (PSIG)		TUBING PRESSURE (PSIG)																				
MO.	DAY	YR.	MO.	DAY	YR.	PSIG	PSIG																				
11	12	13	14	15	16	17	18	19	20	21	22	23	28	29	34	35	38	39	44	45	49	50	53	54	55		
X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	X	E	E			
18	10	79	01	15	910																						

PER AMP	25425		01000		REMARKS:
	SHUT-IN TAKEN B-ROPE INHIBIT DRILLING				
No Tubing in well when shut-in.					

NATURAL BUTTES UNIT
COASTAL OIL & GAS CORPORATION - OPERATED (COGC)
COLORADO INTERSTATE GAS EXPLORATION - OPERATED (CIGE)

Natural Duck

COGC 1-22-9-20

COGC 2-22-9-20

Natural Buttes

COGC NBU (Ute Trail) #1W

COGC NBU (Ute Trail) #1MV

COGC NBU (Ute Trail) #7

COGC NBU (Ute Trail) #52X

COGC NBU (Ute Trail) #83X

COGC NBU (Ute Trail) #88X

COGC NBU #1

COGC NBU #3

COGC NBU #4

COGC NBU #6

COGC NBU #7

COGC NBU #8

COGC NBU #9

COGC NBU #10

COGC NBU #11

COGC NBU #12

COGC NBU #13

COGC NBU #14

COGC NBU #15

COGC NBU #16

COGC NBU #17

COGC NBU #18

COGC NBU #19

COGC NBU #20

COGC NBU #22

COGC NBU #23 N

COGC NBU #24 N2

COGC NBU #26

Highland (Coastal Operated)

NBU #27

NBU #27A

NBU #28

NBU #29

NBU #31

COGC NBU #32Y

COGC NBU #33Y

COGC NBU #35Y

COGC NBU #36Y

COGC NBU #37XP

COGC NBU #38 N2

COGC NBU #39 N

COGC NBU #41J

COGC NBU #43 N

COGC NBU #45 N

COGC NBU #46 N

RECEIVED
FEB 14 1961

DIVISION OF
OIL, GAS & MINING

COGC NBU #47 N2
COGC NBU #48 N3
COGC NBU #49 V
COGC NBU #50 N2
COGC NBU #51 J
COGC NBU #52 J
COGC NBU #53 N
COGC NBU #54 N
COGC NBU #56 N2
COGC NBU #57 N
COGC NBU #58 N2
COGC NBU #62 N
COGC NBU #63 N3
COGC NBU #64 N3
COGC NBU #65 N3
COGC NBU #68 N2
COGC NBU #69 N2
COGC NBU #70 N3
COGC NBU #72 N3
COGC NBU #74 N3
COGC NBU #75 N3
COGC NBU #80 V
COGC NBU #81 V
COGC NBU #83 J
COGC NBU #84 V
COGC NBU #85 J
COGC NBU #86 J
COGC NBU #87 J
COGC NBU #98 V

CIGE NBU #2-29-20-21
CIGE NBU #3-32-9-22
CIGE NBU #4-9-10-21
CIGE NBU #5-31-9-22
CIGE NBU #6-19-9-21
CIGE NBU #7-8-10-21
CIGE NBU #8-35-9-22
CIGE NBU #9-36-9-22
CIGE NBU #10-2-10-22
CIGE NBU #11-14-9-20 (W)
CIGE NBU #13-7-10-21
CIGE NBU #14-9-10-22
CIGE NBU #15-8-10-22
CIGE NBU #16-20-10-22
CIGE NBU #18-2-10-21
CIGE NBU #19-16-9-21
CIGE NBU #20-20-10-22
CIGE NBU #21-15-10-22
CIGE NBU #22-15-9-10
CIGE NBU #23-7-10-22
CIGE NBU #24-29-9-22
CIGE NBU #25-34-9-22
CIGE NBU #27-33-9-22
CIGE NBU #28-35-9-21
CIGE NBU #30-6-10-21
CIGE NBU #31-1-10-22
CIGE NBU #32A-20-9-20

CIGE NBU #33-27-10-21
CIGE NBU #34-13-10-20
CIGE NBU #35-1-10-20
CIGE NBU #36D-32-9-22
CIGE NBU #37D-21-9-21P
CIGE NBU #38-4-10-21
CIGE NBU #40-3-10-21
CIGE NBU #41-12-10-21
CIGE NBU #42-25-9-21
CIGE NBU #43-14-10-22
CIGE NBU #44-9-9-21
CIGE NBU #45-15-9-21
CIGE NBU #46-21-9-21
CIGE NBU #47-14-10-21
CIGE NBU #48-15-10-21
CIGE NBU #49-22-10-21
CIGE NBU #51D-31-9-22P
CIGE NBU #52-5-10-22
CIGE NBU #53-6-10-22
CIGE NBU #54D-35-9-21
CIGE NBU #55-1-10-21
CIGE NBU #56-34-9-21
CIGE NBU #57-10-10-21
CIGE NBU #58-16-10-21
CIGE NBU #59-21-10-21
CIGE NBU #60-14-9-21
CIGE NBU #61-13-9-21
CIGE NBU #62D-36-9-22P
CIGE NBU #63D-29-9-22P
CIGE NBU #64D-33-9-22P
CIGE NBU #65-19-10-22
CIGE NBU #66-23-10-21
CIGE NBU #67A-2-10-22P
CIGE NBU #68D-35-9-22P
CIGE NBU #69-19-10-21
CIGE NBU #70-20-9-21
CIGE NBU #71-7-9-21
CIGE NBU #72-18-9-21
CIGE NBU #73D-5-10-22P
CIGE NBU #74D-6-10-22P
CIGE NBU #75D-8-10-21P
CIGE NBU #76D-9-10-21P
CIGE NBU #77D-10-10-21P
CIGE NBU #78C-16-9-21P
CIGE NBU #79D-1-10-21P
CIGE NBU #80D-2-10-21
CIGE NBU #81D-4-10-21
CIGE NBU #83D-7-10-22P
CIGE NBU #84D-12-10-21P
CIGE NBU #85D-29-10-21
CIGE NBU #86D-16-9-21P
CIGE NBU #87D-34-9-21P
CIGE NBU #88D-15-10-21P
CIGE NBU #89D-34-9-22J

105, JOE, 13 30508

CIGE NBU #90D-9-9-21J
CIGE NBU #91D-15-9-21J
CIGE NBU #92D-13-10-20J
CIGE NBU #93D-2-10-21J
CIGE NBU #94D-14-10-21J
CIGE NBU #95D-14-10-21J
CIGE NBU #99D-25-9-21J

COGC NBU #11-14-9-20

Bluebell (Coastal Operated)

Asay

Powell Fee #3

Powell Fee #4

Ute Tribal #1-31

Powell Fee #3 SWD



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

VERNAL DISTRICT OFFICE

170 South 500 East

Vernal, Utah 84078

IN REPLY
REFER TO:

3162.32
(U-8020)
Oil and Gas Lease
U-4485ST
U-02270A
U-02278ST

RECEIVED
DEC 30 1986

DIVISION OF
OIL, GAS & MINING

December 23, 1986

Mr. R. J. Lewis
Coastal Oil and Gas
P.O. Box 1138
Vernal, Utah 84078

Re: Request for NTL-2B Approval
Drain Pit Near Condensate Tank
CIGE Well 92-13-10-20 (Lease U-4485-ST)
~~CIGE Well 34-13-10-20~~ (Lease U-02270A)
Sec. 13, T.10S., R.20E.
Natural Buttes Unit Well 75N3 (Lease U-02278ST)
Sec. 20, T.10S., R.21E.

Dear Mr. Lewis:

We have reviewed your requests for permission to drain produced water from the condensate tank into a small unlined pit at each of the three above mentioned locations. Your requests are approved subject to the guidelines and requirements provided for in Section V, NTL-2B on these Federal Mineral Leases.

The fences around these smaller pits are presently loose. One of the requirements of conditions of this approval provided for in Section V is that fences around the pits shall receive regular maintenance as needed. The State of Utah Division of Oil, Gas and Mining is the surface management agency at each of the above mentioned three locations, although federal minerals are involved. Therefore, the State of Utah shares enforcement responsibilities with the Bureau of Land Management with regard to regular maintenance of the facilities located on the pads at these locations.

Sincerely,

Karl F. Wright
For Paul M. Andrews
Area Manager
Bookcliffs Resource Area

cc: ✓ John Baza, Div. Oil, Gas & Mining

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form Approved.
Budget Bureau No. 42-R1424

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☒ other ☐ DEC 30 1986

2. NAME OF OPERATOR
Coastal Oil & Gas DIVISION OF

3. ADDRESS OF OPERATOR
P.O. Box 1138 Vernal, Utah 84078

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE:
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON* Pits	<input type="checkbox"/>	<input type="checkbox"/>
(other)	<input type="checkbox"/>	<input type="checkbox"/>

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Permission is requested to retain the use of the small drain pits located near condensate tanks in the Natural Buttes Unit, for the following reasons:

- 1) drain off of BS&W
- 2) impossible to drain to emergency pit due to difference in elevation
- 3) drain off of excess water during winter operations

Pits will be fenced and clean of trash

cc: attachment

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Area Foreman DATE 6/12/85

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

85-06-70-N

*See Instructions on Reverse Side

5. LEASE

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
Natural Buttes Unit

8. FARM OR LEASE NAME

9. WELL NO.
34-13-10-20

10. FIELD OR WILDCAT NAME
Natural Buttes Field

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
10s 20E 4N 13

12. COUNTY OR PARISH
Uintah

13. STATE
Utah

14. API NO.
43-047-30508


15. ELEVATIONS (SHOW DF, KDB, AND WD)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

JUN 1985

CUG 34 SEC 13, T105, R20E Publy 12/8/88

— N



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: El Paso Production Oil & Gas Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 8 South 1200 East CITY Vernal STATE Utah ZIP 84078		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ COUNTY: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____ STATE: UTAH		8. WELL NAME and NUMBER: Exhibit "A"
PHONE NUMBER: 435-789-4433		9. API NUMBER:
		10. FIELD AND POOL, OR WILDCAT:



11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: Name Change
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

As a result of the merger between The Coastal Corporation and a wholly owned subsidiary of El Paso Energy Corporation, the name of Coastal Oil & Gas Corporation has been changed to El Paso Production Oil & Gas Company effective March 9, 2001.

See Exhibit "A"

Bond # 400JU0708

Coastal Oil & Gas Corporation	
NAME (PLEASE PRINT) John T. Elzner	TITLE Vice President
SIGNATURE 	DATE 06-15-01
El Paso Production Oil & Gas Company	
NAME (PLEASE PRINT) John T. Elzner	TITLE Vice President
SIGNATURE 	DATE 06-15-01

This space for State use only

RECEIVED

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING

State of Delaware
Office of the Secretary of State

PAGE 1

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "COASTAL OIL & GAS CORPORATION", CHANGING ITS NAME FROM "COASTAL OIL & GAS CORPORATION" TO "EL PASO PRODUCTION OIL & GAS COMPANY", FILED IN THIS OFFICE ON THE NINTH DAY OF MARCH, A.D. 2001, AT 11 O'CLOCK A.M.

RECEIVED

MAR 1 2001

DIVISION OF
OIL, GAS AND MINING



Harriet Smith Windsor
Harriet Smith Windsor, Secretary of State

0610204 8100

AUTHENTICATION: 1061007

010162788

DATE: 04-03-01

CERTIFICATE OF AMENDMENT

OF

CERTIFICATE OF INCORPORATION

COASTAL OIL & GAS CORPORATION (the "Company"), a corporation organized and existing under and by virtue of the General Corporation Law of the State of Delaware, DOES HEREBY CERTIFY:

FIRST: That the Board of Directors of the Company, by the unanimous written consent of its members, filed with the minutes of the Board, adopted a resolution proposing and declaring advisable the following amendment to the Certificate of Incorporation of the Company:

RESOLVED that it is deemed advisable that the Certificate of Incorporation of this Company be amended, and that said Certificate of Incorporation be so amended, by changing the Article thereof numbered "FIRST." so that, as amended, said Article shall be and read as follows:


"FIRST. The name of the corporation is El Paso Production Oil & Gas Company."

SECOND: That in lieu of a meeting and vote of stockholders, the stockholders entitled to vote have given unanimous written consent to said amendment in accordance with the provisions of Section 228 of the General Corporation Law of the State of Delaware.

THIRD: That the aforesaid amendment was duly adopted in accordance with the applicable provisions of Sections 242 and 228 of the General Corporation Law of the State of Delaware.

IN WITNESS WHEREOF, said COASTAL OIL & GAS CORPORATION has caused this certificate to be signed on its behalf by a Vice President and attested by an Assistant Secretary, this 9th day of March 2001.

COASTAL OIL & GAS CORPORATION



David L. Siddall
Vice President

Attest:


Margaret E. Roark, Assistant Secretary

RECEIVED

STATE OF DELAWARE
SECRETARY OF STATE
DIVISION OF CORPORATIONS
FILED 11:00 AM 03/09/2001
010118394 - 0610204

JUN 19 2001

DIVISION OF
OIL, GAS AND MINING



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

RECEIVED

JUL 12 2001

**DIVISION OF
OIL, GAS AND MINING**

In Reply Refer To:
3106
UTSL-065841
(UT-924)

JUL 10 2001

NOTICE

El Paso Production Oil & Gas Company : Oil and Gas
Nine Greenway Plaza :
Houston TX 77046-0095 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Coastal Oil & Gas Corporation into El Paso Production Oil & Gas Company with El Paso Production Oil & Gas Company being the surviving entity.

For our purposes, the name change is recognized effective March 9, 2001.

The oil and gas lease files identified on the enclosed exhibit have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Coastal Oil & Gas Corporation to El Paso Production Oil & Gas Company. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Wyoming and Colorado.



Opolonia L. Abeyta
Acting Chief, Branch of
Minerals Adjudication

Enclosure

1. Exhibit of Leases (1 pp)

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
~~State of Utah, DOGM,~~ Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

Exhibit of Leases

UTUSL-065841A	UTU-47172	UTU-74415	UTU-53860
UTU-28652	UTU-50687	UTU-74416	UTU-66401
UTU-37943	UTU-52298	UTU-75091	UTU-67868
UTU-44089	UTU-0109054	UTU-75096	UTU-65389
UTU-44090A	UTU-0143511	UTU-75097	UTU-77084
UTU-61263	UTU-0143512	UTU-75673	UTU-61430
UTU-00343	UTU-38401	UTU-76259	UTU-72633
UTU-02651	UTU-38411	UTU-76260	UTU-72650
UTU-02651B	UTU-38418	UTU-76261	UTU-49692
UTU-0142175	UTU-38419	UTU-76493	UTU-57894
UTU-70235	UTU-38420	UTU-76495	UTU-76829
UTU-70406	UTU-38421	UTU-76503	UTU-76830
UTU-74954	UTU-38423	UTU-78228	UTU-76831
UTU-75132	UTU-38424	UTU-78714	
UTU-75699	UTU-38425	UTU-78727	
UTU-76242	UTU-38426	UTU-78734	
UTU-78032	UTU-38427	UTU-79012	
UTU-4377	UTU-38428	UTU-79011	
UTU-4378	UTU-53861	UTU-71694	
UTU-7386	UTU-58097	UTU-00576	
UTU-8344A	UTU-64376	UTU-00647	
UTU-8345	UTU-65222	UTU-01470D	
UTU-8347	UTU-65223	UTU-0136484	
UTU-8621	UTU-66746	UTU-8344	
UTU-14646	UTU-67178	UTU-8346	
UTU-15855	UTU-67549	UTU-8648	
UTU-25880	UTU-72028	UTU-28212	
UTU-28213	UTU-72632	UTU-30289	
UTU-29535	UTU-73009	UTU-31260	
UTU-29797	UTU-73010	UTU-33433	
UTU-31736	UTU-73013	UTU-34711	
UTU-34350	UTU-73175	UTU-46699	
UTU-34705	UTU-73434	UTU-78852	
UTU-37116	UTU-73435	UTU-78853	
UTU-37355	UTU-73444	UTU-78854	
UTU-37573	UTU-73450	UTU-075939	
UTU-38261	UTU-73900	UTU-0149767	
UTU-39223	UTU-74409	UTU-2078	
UTU-40729	UTU-74410	UTU-44426	
UTU-40736	UTU-74413	UTU-49530	
UTU-42469	UTU-74414	UTU-51026	

OPERATOR CHANGE WORKSHEET**ROUTING**

1. GLH		4-KAS
2. CDW	✓	5-LP ✓
3. JLT		6-FILE

Enter date after each listed item is completed

Change of Operator (Well Sold)

Designation of Agent

Operator Name Change (Only)

X **Merger**The operator of the well(s) listed below has changed, effective: **3-09-2001**

FROM: (Old Operator):
COASTAL OIL & GAS CORPORATION
Address: 9 GREENWAY PLAZA STE 2721
HOUSTON, TX 77046-0995
Phone: 1-(713)-418-4635
Account N0230

TO: (New Operator):
EL PASO PRODUCTION OIL & GAS COMPANY
Address: 9 GREENWAY PLAZA STE 2721 RM 2975B
HOUSTON, TX 77046-0995
Phone: 1-(832)-676-4721
Account N1845

CA No.**Unit: NATURAL BUTTES****WELL(S)**

NAME	API NO	ENTITY NO	SEC TWN RNG	LEASE TYPE	WELL TYPE	WELL STATUS
NBU CIGE 34-13-10-20	43-047-30508	2900	13-10S-20E	FEDERAL	GW	P
CIGE 103D-13-10-20	43-047-31742	2900	13-10S-20E	FEDERAL	GW	P
CIGE 154-13-10-20	43-047-32119	2900	13-10S-20E	FEDERAL	GW	P
NBU 328-13E	43-047-32386	2900	13-10S-20E	FEDERAL	GW	P
NBU 360-13E	43-047-32387	2900	13-10S-20E	FEDERAL	GW	P
CIGE 187-13-10-20	43-047-32607	2900	13-10S-20E	FEDERAL	GW	P
CIGE 230-13-10-20	43-047-32885	2900	13-10S-20E	FEDERAL	GW	P
NBU 393-13E	43-047-33071	2900	13-10S-20E	FEDERAL	GW	P
NBU 394-13E	43-047-33072	2900	13-10S-20E	FEDERAL	GW	P
NBU 212	43-047-32399	2900	24-10S-20E	FEDERAL	GW	P
NBU 296 GR	43-047-32886	2900	24-10S-20E	FEDERAL	GW	S
NBU 271	43-047-32887	2900	24-10S-20E	FEDERAL	GW	P
NBU 71-26B	43-047-30578	2900	26-10S-20E	FEDERAL	GW	P
NBU 43	43-047-30848	2900	26-10S-20E	FEDERAL	GW	P
NBU 211 (CA NW-127)	43-047-32339	2900	01-10S-21E	FEDERAL	GW	P
NBU 264	43-047-33000	2900	01-10S-21E	FEDERAL	GW	P
NBU 329 (CA NW-127)	43-047-33227	2900	01-10S-21E	FEDERAL	GW	P
NBU CIGE 40-3-10-21	43-047-30740	2900	03-10S-21E	FEDERAL	GW	P
NBU CIGE 93D-3-10-21J	43-047-31163	2900	03-10S-21E	FEDERAL	GW	P
COG NBU 101	43-047-31755	2900	03-10S-21E	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/19/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/19/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 06/21/2001
4. Is the new operator registered in the State of Utah: YES Business Number: 608186-0143

5. If **NO**, the operator was contacted contacted on: N/A
6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the (merger, name change, or operator change for all wells listed on Federal or Indian leases on: 07/10/2001
7. **Federal and Indian Units:** The BLM or BIA has approved the successor of unit operator for wells listed on: 07/10/2001
8. **Federal and Indian Communization Agreements ("CA"):** The BLM or the BIA has approved the operator change for all wells listed involved in a CA on: 07/10/2001
9. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 08/02/2001
2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 08/02/2001
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE BOND VERIFICATION:

1. State well(s) covered by Bond No.: N/A

FEDERAL BOND VERIFICATION:

1. Federal well(s) covered by Bond No.: WY 2793

FEE WELLS - BOND VERIFICATION/LEASE INTEREST OWNER NOTIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond No: N/A
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A
3. (R649-2-10) The **FORMER** operator of the Fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: _____

FILMING:

1. All attachments to this form have been **MICROFILMED** on: _____

FILING:

1. **ORIGINALS/COPIES** of all attachments pertaining to each individual well have been filled in each well file on: _____

COMMENTS: Master list of all wells involved in operator change from Coastal Oil & Gas Corporation to El Paso Production Oil and Gas Company shall be retained in the "Operator Change File".

JAN. 17. 2003 3:34PM

PORT

NO. 173

P. 2

**WESTPORT OIL AND GAS COMPANY, L.P.**

410 Seventeenth Street #2300 Denver Colorado 80202-4436
Telephone: 303 573 5404 Fax: 303 573 5609

February 1, 2002

Department of the Interior
Bureau of Land Management
2850 Youngfield Street
Lakewood, CO 80215-7093
Attention: Ms. Martha Maxwell

**RE: BLM Bond CO-1203
BLM Nationwide Bond 158626364
Surety - Continental Casualty Company
Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Conversion of Westport Oil and Gas Company, Inc., into Westport Oil and Gas Company, L.P.
Assumption Rider - Westport Oil and Gas Company, L.P.**

Dear Ms. Maxwell:

Pursuant to our recent conversations, please find the following list of enclosures for the BLM's consideration and approval:

Two (2) Assumption Riders, fully executed originals.
Copies of Belco Energy Corporation merger into Westport Oil and Gas Company, Inc.
Copies of Westport Oil and Gas Company, Inc., conversion into Westport Oil and Gas Company, L.P.
List of all Federal/BIA/State Leases - Belco/Westport's leases - in all states.

Please inform us of any additional information needed to complete the change to Westport Oil and Gas Company, L.P., as operator of record.

I thank you for your assistance and cooperation in this matter. Please do not hesitate contacting the undersigned, should a question arise.

Sincerely,
Westport Oil and Gas Company, L.P.

Debby J. Black
Engineer Technician

Encl;



United States Department of the Interior **RECEIVED**

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

FEB 22 2002

DIVISION OF
OIL, GAS AND MINING

In Reply Refer To:

3106

UTU-25566 et al

(UT-924)

FEB 21 2002

NOTICE

Westport Oil and Gas Company L.P. : Oil and Gas
410 Seventeenth Street, #2300 :
Denver Colorado 80215-7093 :

Name Change Recognized

Acceptable evidence has been received in this office concerning the name change of Westport Oil and Gas Company, Inc. into Westport Oil and Gas Company, L.P. with Westport Oil and Gas Company, L.P. being the surviving entity.


For our purposes, the name change is recognized effective December 31, 2001.

The oil and gas lease files identified have been noted as to the name change. The exhibit was compiled from a list of leases obtained from our computer program. We have not abstracted the lease files to determine if the entities affected by this name change hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested recorded title or operating rights interests. We will be notifying the Minerals Management Service and all applicable Bureau of Land Management offices of the change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify additional leases in which the entities maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Westport Oil and Gas Company, Inc. to Westport Oil and Gas Company, L.P.. You may accomplish this either by consent of surety rider on the original bond or a rider to the original bond. The bonds are held in Colorado.

UTU-03405
UTU-20895
UTU-25566
UTU-43156
UTU-49518
UTU-49519
UTU-49522
UTU-49523



Robert Lopez
Chief, Branch of
Minerals Adjudication

cc: Moab Field Office
Vernal Field Office
MMS, Reference Data Branch, MS3130, PO Box 5860, Denver CO 80217
State of Utah, DOGM, Attn: Jim Thompson (Ste. 1210), Box 145801, SLC UT 84114
Teresa Thompson (UT-922)
Joe Incardine (UT-921)

memorandum

Branch of Real Estate Services
Uintah & Ouray Agency

Date: 5 December, 2002

Reply to
Attn of: Supervisory Petroleum Engineer

Subject: Modification of Utah Division of Oil, Gas and Mining Regulations

To: Director, Utah Division of Oil, Gas and Mining Division: John Baza

We have been advised of changes occurring with the operation of your database for Change of Operator. You will be modifying your records to reflect Change of Operator once you have received all necessary documentation from the companies involved, and perhaps in advance of our Notice of Concurrence/Approval of Change of Operator where Indian leases are involved.


We have no objection.

With further comment to Rulemaking, I wish to comment concerning the provision of Exhibits for upcoming Hearings. I would like to see the Uintah & Ouray Agency, BIA, and the Ute Indian Tribe, Energy & Mineral Resources Department added to the list of those parties that receive advance Exhibits so as to allow us to have research time prior to Hearing dates. We will be able to provide a more informed recommendation to the Oil, Gas and Mining Board. It would be best if we would receive only those Exhibits that concern Indian lands, specifically on or adjacent to Indian lands. This may be a difficult situation to attain, as it is not always clear where 'on or adjacent' occurs.

I am aware that you have gone to extra effort to correct this matter already, and I fully appreciate it. My request is intended only to allow the addition of Uintah & Ouray Agency and Ute Indian Tribe to the official listing.

We appreciate your concern, and hope that these comments are timely enough for consideration in the revision process.

CC: Minerals & Mining Section of RES
Ute Energy & Mineral Resources Department: Executive Director
chrono





United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Washington, D.C. 20240

FEB 10 2003IN REPLY REFER TO:
Real Estate Services

Carroll A. Wilson
Principal Landman
Westport Oil and Gas Company, L.P.
1368 South 1200 East
Vernal, Utah 84078

Dear Mr. Wilson:

This is in response to your request for approval of RLI Insurance Company's Nationwide Oil and Gas Lease Bond No. RLB0005239 executed effective December 17, 2002, (\$150,000 coverage) with Westport Oil and Gas Company, L. P., as principal.

This bond is hereby approved as of the date of this correspondence and will be retained in the Bureau of Indian Affairs' Division of Real Estate Services, 1849 C Street, NW, MS-4512-MIB, Washington, D.C. 20240. All Bureau oil and gas regional offices and the surety are being informed of this action.

In cases where you have existing individual and/or collective bonds on file with one or more of our regional offices, you may now request those offices, directly, to terminate in lieu of coverage under this Nationwide Bond.

Enclosed is a copy of the approved bond for your files. If we may be of further assistance in this matter, please advise.

Sincerely,

ACTING

Director, Office of Trust Responsibilities

Enclosure

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

8. WELL NAME and NUMBER:

Exhibit "A"

9. API NUMBER:

10. FIELD AND POOL, OR WILDCAT:

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

El Paso Production Oil & Gas Company

3. ADDRESS OF OPERATOR:

9 Greenway Plaza

CITY Houston

STATE TX

ZIP 77064-0995

PHONE NUMBER:

(832) 676-5933

4. LOCATION OF WELL

FOOTAGES AT SURFACE:

COUNTY:

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☒ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER:

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Operator change to Westport Oil and Gas Company, L.P., 1670 Broadway, Suite 2800, Denver, CO. 80202-4800, effective December 17, 2002.

BOND #

State Surety Bond No. RLB0005236

Fee Bond No. RLB0005238

EL PASO PRODUCTION OIL & GAS COMPANY

By: 
Jon R. Nelsen, Attorney-in-Fact

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

WESTPORT OIL AND GAS COMPANY, L.P.

NAME (PLEASE PRINT)

David R. Dix

TITLE Agent and Attorney-in-Fact

SIGNATURE



DATE

12/17/02

(This space for State use only)



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

February 27, 2003

Westport Oil and Gas Company, L.P.
Attn: Gary D. Williamson
1670 Broadway, Suite 2800
Denver, Colorado 80202

Re: Natural Buttes Unit
Uintah County, Utah

Gentlemen:

On February 27, 2003, we received an indenture dated December 17, 2002, whereby El Paso Production Oil & Gas Company resigned as Unit Operator and Westport Oil and Gas Company, L.P., was designated as Successor Unit Operator for the Natural Buttes Unit, Uintah County, Utah.

This indenture was executed by all required parties and the signatory parties have complied with Sections 5 and 6 of the unit agreement. The instrument is hereby approved effective February 27, 2003. In approving this designation, the Authorized Officer neither warrants nor certifies that the designated party has obtained all required approval that would entitle it to conduct operations under the Natural Buttes Unit Agreement.

Your nationwide (Colorado) oil and gas bond No. 1203 will be used to cover all operations within the Natural Buttes Unit.

It is requested that you notify all interested parties of the change in unit operator. Copies of the approved instruments are being distributed to the appropriate federal offices, with one copy returned herewith.

Sincerely,

/s/ Robert A. Henricks

Robert A. Henricks
Chief, Branch of Fluid Minerals

Enclosure

bcc: Field Manager - Vernal (w/enclosure)
SITLA
Division of Oil, Gas & Mining
Minerals Adjudication Group
File - Natural Buttes Unit (w/enclosure)
Agr. Sec. Chron
Fluid Chron

UT922:TAThompson:tt:02/27/2003

RECEIVED

FEB 28 2003

DIV. OF OIL, GAS & MINING

Form 3160-5
(August 1999)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

*Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.*FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

SEE ATTACHED EXHIBIT "A"

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

SEE ATTACHED EXHIBIT "A"

9. API Well No.

SEE ATTACHED EXHIBIT "A"

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UT

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7023

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED EXHIBIT "A"

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	SUCCESSOR OF
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed when testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator determined that the site is ready for final inspection.

WESTPORT OIL & GAS COMPANY, L.P., IS CONSIDERED TO BE THE OPERATOR ON THE ATTACHED DESCRIBED LANDS AND IS RESPONSIBLE UNDER THE TERMS AND CONDITIONS OF THE LEASE FOR THE OPERATIONS CONDUCTED ON THE LEASED LANDS OR PORTIONS THEREOF, BOND COVERAGE FOR THIS WELL IS PROVIDED BY FEDERAL NATIONWIDE BOND NO. 158626364, EFFECTIVE FEBRUARY 1, 2002, AND BIA NATIONWIDE BOND NO. RLB0005239, EFFECTIVE FEBRUARY 10, 2003.

RECEIVED

MAR 04 2003

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

CHERYL CAMERON

Title

OPERATIONS

Date

March 4, 2003

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW ✓

3. FILE

X Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective: **12-17-02****FROM: (Old Operator):**

EL PASO PRODUCTION OIL & GAS COMPANY

Address: 9 GREENWAY PLAZA

HOUSTON, TX 77064-0995

Phone: 1-(832)-676-5933

Account No. N1845

TO: (New Operator):

WESTPORT OIL & GAS COMPANY LP

Address: P O BOX 1148

VERNAL, UT 84078

Phone: 1-(435)-781-7023

Account No. N2115

CA No.

Unit:

NATURAL BUTTES

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
NBU 523-12E	12-10S-20E	43-047-33685	2900	FEDERAL	GW	P
NBU 516-12E	12-10S-20E	43-047-33696	2900	FEDERAL	GW	P
NBU 524-12E	12-10S-20E	43-047-33701	2900	FEDERAL	GW	P
NBU 328-13E	13-10S-20E	43-047-32386	2900	FEDERAL	GW	P
NBU 360-13E	13-10S-20E	43-047-32387	2900	FEDERAL	GW	P
CIGE 154-13-10-20	13-10S-20E	43-047-32119	2900	FEDERAL	GW	P
NBU CIGE 92D-13-10-20J	13-10S-20E	43-047-31162	2900	STATE	GW	P
CIGE 103D-13-10-20	13-10S-20E	43-047-31742	2900	FEDERAL	GW	P
NBU 26-13B	13-10S-20E	43-047-30364	2900	FEDERAL	GW	P
NBU CIGE 34-13-10-20	13-10S-20E	43-047-30508	2900	FEDERAL	GW	P
CIGE 187-13-10-20	13-10S-20E	43-047-32607	2900	FEDERAL	GW	P
CIGE 230-13-10-20	13-10S-20E	43-047-32885	2900	FEDERAL	GW	P
NBU 393-13E	13-10S-20E	43-047-33071	2900	FEDERAL	GW	P
NBU 394-13E	13-10S-20E	43-047-33072	2900	FEDERAL	GW	P
NBU 64-24B	24-10S-20E	43-047-30444	2900	FEDERAL	GW	PA
NBU 74N3	24-10S-20E	43-047-31087	2900	STATE	GW	P
NBU 212	24-10S-20E	43-047-32399	2900	FEDERAL	GW	P
NBU 271	24-10S-20E	43-047-32887	2900	FEDERAL	GW	P
NBU 65-25B	25-10S-20E	43-047-30467	2900	FEDERAL	GW	PA
NBU 71-26B	26-10S-20E	43-047-30578	2900	FEDERAL	GW	P

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 02/28/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 03/04/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 03/06/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
5. If **NO**, the operator was contacted contacted on: _____

6. (R649-9-2) Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM-12/31/2003 BIA-12/5/02

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 02/27/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 03/19/2003
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 03/19/2003
3. Bond information entered in RBDMS on: N/A
4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: RLB 0005236

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 158626364

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: RLB 0005239

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB 0005238
2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY, L.P.

3a. Address

P.O. BOX 1148 VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Multiple Wells - see attached

5. Lease Serial No.

Multiple Wells - see attached

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

891008900A

8. Well Name and No.

Multiple Wells - see attached

9. API Well No.

Multiple Wells - see attached

10. Field and Pool, or Exploratory Area

Natural Buttes Unit

11. County or Parish, State

Uintah County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

Westport Oil & Gas requests a variance to Onshore Order No. 4, Part IIIC.a. requiring each sales tank be equipped with a pressure-vacuum thief hatch and/or vent line valve. The variance is requested as an economic analysis shows the value of the shrunk condensate will not payout the incremental cost of purchasing and maintaining the valve resulting in a loss of value over the producing life of the well.

The volume lost to shrinkage by dropping the tank pressure from 6 ozs. to 0 psig is shown to be 0.3% of the tank volume. This was determined by lab analysis of a representative sample from the field. The sample shrunk from 98.82% of original volume to 98.52% when the pressure was dropped. The average NBU well produces approximately 6 bbls condensate per month. The resulting shrinkage would amount to 0.56 bbls per month lost volume due to shrinkage. The value of the shrunk and lost condensate does not recoup or payout the cost of installing and maintaining the valves and other devices that hold the positive tank pressure. An economic run based on the loss and costs is attached. Westport Oil & gas requests approval of this variance in order to increase the value of the well to the operator and the mineral royalty owners.

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

J.T. Conley

Signature

J.T. Conley

COPY SENT TO OPERATOR

Date:

Initials:

CHD

Title

Date

9-2-2003

Operations Manager

SEP 10 2003

DIV. OF OIL, GAS & MINING

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval of This
Action is Necessary

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Date:

9/16/03

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CIGE 011GR	14-9-20 SWSL	UTU00177A	891008900A	430473042100S1
CIGE 013	7-10-21 NESE	UTU02270A	891008900A	430473042000S1
CIGE 014	9-10- JESW	UTU01196B	891008900A	430473048400S1
CIGE 018	2-10-21 NWNW	ML22652	891008900A	430473047100S1 ✓
CIGE 019	16-9-21 SWSW	ML3141A	891008900A	430473045900S1
CIGE 020	20-10-21 SESW	UTU02278	891008900A	430473048500S1
CIGE 022	15-9-20 SENW	UTU0144868	891008900A	430473049700S1
CIGE 023	7-10-22 SESE	ML23609	891008900A	430473033300S1 ✓
CIGE 024	29-9-22 SESW	U01207	891008900A	430473049300S1
CIGE 025	34-9-22 SENW	UTU0149077	891008900A	430473073700S1
CIGE 027	33-9-22 NENW	UTU01191A	891008900A	430473073800S1
CIGE 028	35-9-21 NESE	ML22582	891008900A	430473073900S1 ✓
CIGE 030	6-10-21 NENW	UTU01791	891008900A	430473049800S1
CIGE 031	1-10-22 SWNW	U011336	891008900A	430473051100S1
CIGE 032A	20-9-20 NESW	UTU01567A	891008900A	430473049600S1
CIGE 034	13-10-20 SWNE	UTU02270A	891008900A	430473050800S1
CIGE 035	1-10-20 NESW	UTU02270A	891008900A	430473049400S1
CIGE 036D	32-9-22 NWNW	ML22649	891008900A	430473083300S1 ✓
CIGE 037D	21-9-21 SWSE	UTU0576	891008900A	430473091000S1
CIGE 038D	4-10-21 SWSE	U01416	891008900A	430473049500S1
CIGE 040	3-10-21 NESW	UTU0149078	891008900A	430473074000S1
CIGE 042	25-9-21 SWSE	U04139	891008900A	430473049200S1 ✓
CIGE 043	14-10-22 SENW	U01197A	891008900A	430473049100S1 ✓
CIGE 044	9-9-21 SESE	UTU01188	891008900A	430473052700S1
CIGE 045	15-9-21 NESE	UTU01193	891008900A	430473052800S1
CIGE 046	21-9-21 NENE	UTU0576	891008900A	430473052900S1
CIGE 047	14-10-21 NWSE	UTU01393C	891008900A	430473051000S1
CIGE 048	15-10-21 SWNE	UTU01416A	891008900A	430473050600S1
CIGE 051D	31-9-22 NENE	U01191	891008900A	430473088900S1 ✓
CIGE 052	5-10-22 SENW	UTU01195	891008900A	430473053100S1
CIGE 053	6-10-22 NESW	UTU01195	891008900A	430473053300S1
CIGE 054D	35-9-21 NENE	ML22582	891008900A	430473085100S1 ✓
CIGE 055	1-10-21 SENW	ML23612	891008900A	430473051200S1 ✓
CIGE 056	34-9-21 SWSE	U01194A	891008900A	430473053000S1 ✓
CIGE 057	10-10-21 NENE	UTU0149079	891008900A	430473054300S1
CIGE 058	16-10-21 SESE	ML10755	891008900A	430473053200S1
CIGE 060	14-9-21 SENW	UTU01193	891008900A	430473054900S1
CIGE 061	13-9-21 SENW	U01193	891008900A	430473055000S1
CIGE 062D	36-9-22 NWSW	ML22650	891008900A	430473088500S1 ✓
CIGE 063D	29-9-22 NWNW	UTU462	891008900A	430473094900S1
CIGE 064D	33-9-22 SWSW	UTU01191A	891008900A	430473095000S1
CIGE 066	23-10-21 SENW	UTU02278A	891008900A	430473054200S1
CIGE 067A	2-10-22 NENE	ML22651	891008900A	430473093800S1
CIGE 068D	35-9-22 NWSW	UTU010954A	891008900A	430473095100S1
CIGE 069	19-10-21 SENW	ML22792	891008900A	430473063500S1
CIGE 070	20-9-21 NESE	UTU0575	891008900A	430473063600S1
CIGE 071	7-9-21 NESE	UTU0575B	891008900A	430473063700S1
CIGE 072	18-9-21 SWNE	UTU0575	891008900A	430473063400S1
CIGE 073D	5-10-22 SWSW	UTU01191A	891008900A	430473095200S1
CIGE 074D	6-10-22 NWSE	UTU01195	891008900A	430473095300S1
CIGE 075D	8-10-21 SENE	UTU01791	891008900A	430473095400S1
CIGE 076D	9-10-21 NENE	UTU01416	891008900A	430473095500S1
CIGE 077D	10-10-21 SESE	UTU0149079	891008900A	430473095600S1
CIGE 078C	16-9-21 NENW	UTU38409	891008900A	430473087000S1
CIGE 079D	1-10-21 NENE	ML23612	891008900A	430473089600S1 ✓
CIGE 080D	2-10-21 NWNW	ML22652	891008900A	430473085300S1 ✓
CIGE 081D	4-10-21 NENE	ML22940	891008900A	430473085400S1
CIGE 086D	16-9-21 SWSE	ML3282	891008900A	430473088600S1
CIGE 087D	34-9-21 NENE	U01194A	891008900A	430473086900S1 ✓
CIGE 088D	15-10-21 NWNW	UTU01791A	891008900A	430473095800S1
CIGE 089D	34-9-22 SENE	UTU0149077	891008900A	430473114600S1
CIGE 090D	9-9-21 NWNE	UTU01188A	891008900A	430473114900S1
CIGE 091D	15-9-21 NWNE	UTU01188	891008900A	430473115100S1

Westport Oil & Gas, L.P.

Project Economics Worksheet

Instructions:

Fill in blue boxed areas with before and after project data. The evaluation results are shown below and graphed automatically at the bottom of the page. This sheet is protected to prevent accidental alteration of the formulas. See JTC for changes. OPX entered as annual costs and/or as unit OPX costs for \$/BF and \$/MCF

Project Name:

Condensate Shrinkage Economics

Is this job a well pull or production rig job ??? ☒ N (Y or N)

	BEFORE \$/Year	AFTER \$/Year	DIFFERENCE \$/Year
Gross Oil Revenue	\$1,088	\$1,099	\$11
Gross Gas Revenue	\$0	\$0	\$0
NGL Revenue	\$0	\$0	\$0
PULING UNIT SERVICE			\$0
WIRELINE SERVICE			\$0
SUBSURF EQUIP REPAIRS			\$0
COMPANY LABOR			\$0
CONTRACT LABOR	\$0	\$200	\$200
CONTR SERVICE			\$0
LEASE FUEL GAS	\$0	\$0	\$0
UTILITIES - ELECTRICITY	\$0	\$0	\$0
CHEMICAL TREATING			\$0
MATERIAL & SUPPLY	\$0	\$150	\$150
WATER & HAULING			\$0
ADMINISTRATIVE COSTS			\$0
GAS PLANT PROCESSING			\$0
Totals	\$0	\$350	\$350

Increased OPX Per Year

Investment Breakdown:

	Cap/Exp Code	Cost, \$
Capital \$	820/830/840	\$1,200
Expense \$	830/840	\$0
Total \$		\$1,200

Oil Price	\$ 23.00	\$/BO
Gas Price	\$ 3.10	\$/MCF
Electric Cost	\$ -	\$/ HP / day
OPX/BF	\$ 2.00	\$/BF
OPX/MCF	\$ 0.62	\$/MCF

Production & OPX Detail:

	Before		After		Difference	
Oil Production	0.192	BOPD	0.194	BOPD	0.002	BOPD
Gas Production	0	MCFPD	0	MCFPD	0	MCFPD
Wtr Production	0	BWPD	0	BWPD	0	BWPD
Horse Power		HP		HP	0	HP
Fuel Gas Burned		MCFPD		MCFPD	0	MCFPD

Project Life:

Life = 20.0 Years
(Life no longer than 20 years)

Internal Rate of Return:

After Tax IROR = #DIV/0!

AT Cum Cashflow:

Operating Cashflow = (\$2,917) (Discounted @ 10%)

Payout Calculation:

$$\text{Payout} = \frac{\text{Total Investment}}{\text{Sum(OPX + Incremental Revenue)}} = 1$$

Payout occurs when total AT cashflow equals investment
See graph below, note years when cashflow reaches zero

Payout = NEVER Years or #VALUE! Days


Gross Reserves:

Oil Reserves = 6 BO
Gas Reserves = 0 MCF
Gas Equiv Reserves = 38 MCFE

Notes/Assumptions:

An average NBU well produces 0.192 Bcpd with no tank pressure. The production is increased to 0.194 Bcpd if 4 ozs of pressure are placed on the tank. The increased production does not payout the valve cost or the estimated annual maintenance costs.

Project: Condensate Shrinkage Economics



Westport Oil and Gas, Inc.

NBU/Ouray Field

RFL 2003-022

COMPARISON OF FLASH BACK PRESSURES

Calculated by Characterized Equation-of-State

Flash Conditions		Gas/Oil Ratio (scf/STbbl) (A)	Specific Gravity of Flashed Gas (Air=1.000)	Separator Volume Factor (B)	Separator Volume Percent (C)
psig	°F				

Calculated at Laboratory Flash Conditions

80	70			1.019	
0	122	30.4	0.993	1.033	101.37%
0	60	0.0	—	1.000	98.14%

Calculated Flash with Backpressure using Tuned EOS

80	70			1.015	
6.0 oz	65	24.6	0.777	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
4.0 oz	65	24.7	0.778	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
2.0 oz	65	24.7	0.779	1.003	98.82%
0	60	0.0	—	1.000	98.52%
80	70			1.015	
0	65	24.8	0.780	1.003	98.82%
0	60	0.0	—	1.000	98.52%

(A) Cubic Feet of gas at 14.696 psia and 60 °F per Barrel of Stock Tank Oil at 60 °F.

(B) Barrels of oil at indicated pressure and temperature per Barrel of Stock Tank Oil at 60 °F.

(C) Oil volume at indicated pressure and temperature as a percentage of original saturated oil volume.

Note: Bubblepoint of sample in original sample container was 80 psig at 70° F with 1 cc water

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

1/6/2006

FROM: (Old Operator):
 N2115-Westport Oil & Gas Co., LP
 1368 South 1200 East
 Vernal, UT 84078
 Phone: 1-(435) 781-7024

TO: (New Operator):
 N2995-Kerr-McGee Oil & Gas Onshore, LP
 1368 South 1200 East
 Vernal, UT 84078
 Phone: 1-(435) 781-7024

CA No.		Unit:		NATURAL BUTTES UNIT			
WELL NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 5/10/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 5/10/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 3/7/2006
- a. Is the new operator registered in the State of Utah: YES Business Number: 1355743-0181
- b. If **NO**, the operator was contacted on:
- a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
- b. Inspections of LA PA state/fee well sites complete on: n/a 3 LA wells & all PA wells transferred
- c. Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM 3/27/2006 BIA not yet
- Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: 3/27/2006
- Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on:

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 5/15/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 5/15/2006
- Bond information entered in RBDMS on: 5/15/2006
- Fee/State wells attached to bond in RBDMS on: 5/16/2006
- Injection Projects to new operator in RBDMS on:
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a Name Change Only

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: CO1203
- Indian well(s) covered by Bond Number: RLB0005239
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number RLB0005236
- a. The **FORMER** operator has requested a release of liability from their bond on: n/a rider added KMG
 The Division sent response by letter on:

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 5/16/2006

COMMENTS:

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

KERR-McGEE OIL & GAS ONSHORE LP

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ Notice of Intent

☒ Subsequent Report

☐ Final Abandonment Notice

TYPE OF ACTION

☐ Acidize

☐ Alter Casing

☐ Casing Repair

☐ Change Plans

☐ Convert to Injection

☐ Deepen

☐ Fracture Treat

☐ New Construction

☐ Plug and Abandon

☐ Plug Back

☐ Production (Start/Resume)

☐ Reclamation

☐ Recomplete

☐ Temporarily Abandon

☐ Water Disposal

☐ Water Shut-Off

☐ Well Integrity

☒ Other CHANGE OF OPERATOR

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

PLEASE BE ADVISED THAT KERR-McGEE OIL & GAS ONSHORE LP, IS CONSIDERED TO BE THE OPERATOR OF THE ATTACHED WELL LOCATIONS. EFFECTIVE JANUARY 6, 2006. KERR-McGEE OIL & GAS ONSHORE LP, IS RESPONSIBLE UNDER TERMS AND CONDITIONS OF THE LEASE(S) FOR THE OPERATIONS CONDUCTED UPON LEASE LANDS. BOND COVERAGE IS PROVIDED BY STATE OF UTAH NATIONWIDE BOND NO. RLB0005237.

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

BLM BOND = C01203

BIA BOND = RLB0005239

APPROVED 5/16/06

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

RANDY BAYNE

Signature

Title

DRILLING MANAGER

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Title

Date

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires November 30, 2000

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or reenter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other instructions on reverse side

1. Type of Well

☐ Oil Well ☒ Gas Well ☐ Other

2. Name of Operator

WESTPORT OIL & GAS COMPANY L.P.

3a. Address

1368 SOUTH 1200 EAST VERNAL, UT 84078

3b. Phone No. (include area code)

(435) 781-7024

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

SEE ATTACHED

5. Lease Serial No.

MULTIPLE LEASES

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

MUTIPLE WELLS

9. API Well No.

10. Field and Pool, or Exploratory Area

11. County or Parish, State

UINTAH COUNTY, UTAH

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other CHANGE OF OPERATOR
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operations (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomplete horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.

EFFECTIVE JANUARY 6, 2006, WESTPORT OIL & GAS COMPANY L.P., HAS RELINQUISHED THE OPERATORSHIP OF THE ATTACHED WELL LOCATIONS TO KERR-McGEE OIL & GAS ONSHORE LP.

APPROVED 5/16/06

Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED

MAY 10 2006

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Name (Printed/Typed)

BRAD LANEY

Signature

Title

ENGINEERING SPECIALIST

Date

May 9, 2006

THIS SPACE FOR FEDERAL OR STATE USE

Approved by

Brad Laney

Title

Date

5-9-06

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

Title 18 U.S.C. Section 1001, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.



United States Department of the Interior

BUREAU OF LAND MANAGEMENT
Colorado State Office
2850 Youngfield Street
Lakewood, Colorado 80215-7076

IN REPLY REFER TO:

CO922 (MM)
3106
COC017387 et. al.

March 23, 2006

NOTICE

Kerr-McGee Oil & Gas Onshore L.P. :
1999 Broadway, Suite 3700 : Oil & Gas
Denver, CO 80202 :

Merger/Name Change - Recognized

On February 28, 2006 this office received acceptable evidence of the following mergers and name conversion:

Kerr-McGee Oil & Gas Onshore L.P., a Delaware Limited Partnership, and Kerr-McGee Oil & Gas Onshore LLC, a Delaware Limited Partnership merger with and into Westport Oil and Gas Company L.P., a Delaware Limited Partnership, and subsequent Westport Oil & Gas Company L.P. name conversion to Kerr-McGee Oil & Gas Onshore L.P.

For our purposes the merger and name conversion was effective January 4, 2006, the date the Secretary of State of Delaware authenticated the mergers and name conversion.

Kerr-McGee Oil & Gas Onshore L.P. provided a list of oil and gas leases held by the merging parties with the request that the Bureau of Land Management change all their lease records from the named entities to the new entity, Kerr-McGee Oil & Gas Onshore L.P. In response to this request each state is asked to retrieve their own list of leases in the names of these entities from the Bureau of Land Management's (BLM) automated LR2000 data base.

The oil and gas lease files identified on the list provided by Kerr-McGee Oil & Gas Onshore L.P. have been updated as to the merger and name conversion. We have not abstracted the lease files to determine if the entities affected by the acceptance of these documents holds an interest in the lease, nor have we attempt to identify leases where the entity is the operator on the ground that maintains vested record title or operating rights interests. If additional documentation, for change of operator, is required you will be contacted directly by the appropriate Field Office. The Mineral Management Services (MMS) and other applicable BLM offices were notified of the merger with a copy of this notice

Please contact this office if you identify additional leases where the merging party maintains an interest, under our jurisdiction, and we will document the case files with a copy of this notice. If the leases are under the jurisdiction of another State Office that information will be forwarded to them for their action.

Three riders accompanied the merger/name conversion documents which will add Kerr-McGee Oil and Gas Onshore LLC as a principal to the 3 Kerr-McGee bonds maintained by the Wyoming State Office. These riders will be forward to them for their acceptance.

The Nationwide Oil & Gas Continental Casualty Company Bond #158626364 (BLM Bond #CO1203), maintained by the Colorado State Office, will remain in full force and effect until an assumption rider is accepted by the Wyoming State Office that conditions their Nationwide Safeco bond to accept all outstanding liability on the oil and gas leases attached to the Colorado bond.

If you have questions about this action you may call me at 303.239.3768.

/s/Martha L. Maxwell
Martha L. Maxwell
Land Law Examiner
Fluid Minerals Adjudication

Attachment:

List of OG Leases to each of the following offices:

MMS MRM, MS 357B-1

WY, UT, NM/OK/TX, MT/ND, WY State Offices

CO Field Offices

Wyoming State Office

Rider #1 to Bond WY2357

Rider #2 to Bond WY1865

Rider #3 to Bond WY1127



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-922)

March 27, 2006

Memorandum

To: Vernal Field Office

From: Chief, Branch of Fluid Minerals

Subject: Merger Approval

Attached is an approved copy of the merger recognized by the Bureau of Land Management, Colorado State Office. We have updated our records to reflect the merger from Westport Oil and Gas Company L.P. into Kerr-McGee Onshore Oil and Gas Company. The merger was approved effective January 4, 2006.

Chief, Branch of
Fluid Minerals

Enclosure

Approval letter from BLM COSO (2 pp)

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare
Dave Mascarenas
Susan Bauman

RECEIVED

MAR 28 2006

ENV. OF CALIF. GAS & MIN. DIV.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: U-022070-A
1. TYPE OF WELL Gas Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P.		7. UNIT or CA AGREEMENT NAME: NATURAL BUTTES
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		8. WELL NAME and NUMBER: CIGE 34
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1823 FNL 2090 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWNE Section: 13 Township: 10.0S Range: 20.0E Meridian: S		9. API NUMBER: 43047305080000
9. FIELD and POOL or WILDCAT: NATURAL BUTTES		COUNTY: UINTAH
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 5/26/2011	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> APD EXTENSION <input type="checkbox"/> WILDCAT WELL DETERMINATION <input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. THE SUBJECT WELL WAS RETURNED TO PRODUCTION ON 05/26/2011.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY		
NAME (PLEASE PRINT) Sheila Wopsock	PHONE NUMBER 435 781-7024	TITLE Regulatory Analyst
SIGNATURE N/A	DATE 6/14/2011	